



**REGIONAL DISTRICT OF CENTRAL KOOTENAY**

**AREA E ADVISORY PLANNING AND HERITAGE  
COMMISSION  
OPEN MEETING AGENDA**

**3:00PM**

**Thursday, September 26, 2024**

**Hybrid Meeting**

To promote openness, transparency and provide accessibility to the public we provide the ability to attend all RDCK meetings in-person or remote.

**Join by Video:**

<https://rdck-bc-ca.zoom.us/j/96613556253?pwd=3H3KqSelUG7fDxUz4R2RtwzCODz29B.1>

**Join by Phone:** 778-907-2071

**Meeting ID:** 966 1355 6253

**Passcode:** 123456

**In-Person Location:** RDCK Board Room, 202 Lakeside Drive, Nelson, BC

**1. CALL TO ORDER**

Chair Rye called the meeting to order at \_\_\_\_ p.m

**2. TRADITIONAL LANDS ACKNOWLEDGEMENT STATEMENT**

We acknowledge and respect the Indigenous peoples within whose traditional lands we are meeting today.

**3. ADOPTION OF AGENDA**

**MOVED** and seconded,  
AND Resolved:

The Agenda for the September 26, 2024 Electoral Area E Advisory Planning and Heritage Commission meeting, be adopted as circulated.

**Carried/Defeated**

**4. RECEIPT OF MINUTES**

The May 30, 2024 Electoral Area E Advisory Planning and Heritage Commission minutes, have been received.

**5. STAFF REPORTS**

**5.1 Watercourse Development Permit Application – DP2307E – Judith and Jerry Levinson**

The Referral Package dated August 9 2024 from Planner Zacharia Giacomazzo, has been received.

**Moved** and seconded,  
AND Resolved:

That the Area E Advisory Planning Commission **SUPPORT/NOT SUPPORT** the Watercourse Development Permit Application to Judith and Jerry Levinson for the property located 2205 Bealby Road, Rural Nelson and legally described as DISTRICT LOT A KOOTENAY DISTRICT PLAN NEP85347

**Carried/Defeated**

**6. PUBLIC TIME**

The Chair will call for questions from the public at \_\_\_\_ p.m.

**7. NEXT MEETING**

The next Electoral Area E Advisory Planning and Heritage Commission Meeting is scheduled for October 31, 2024.

**8. ADJOURNMENT**

**MOVED** and seconded,  
AND Resolved:

The Electoral Area E Advisory Planning and Heritage Commission meeting be adjourned at \_\_\_\_ p.m.



**REGIONAL DISTRICT OF CENTRAL KOOTENAY**

**AREA E ADVISORY PLANNING AND HERITAGE  
COMMISSION  
OPEN MEETING MINUTES**

**3:00PM**

**Thursday, May 30, 2024**

**Hybrid Meeting**

To promote openness, transparency and provide accessibility to the public we provide the ability to attend all RDCK meetings in-person or remote.

**Join by Video:**

<https://rdck-bc-ca.zoom.us/j/98006442231?pwd=cVM2M0lOMTR4eWc0T2Mra1l1WFFBZz09>

**Join by Phone:** 778-907-2071

**Meeting ID:** 980 0644 2231

**Passcode:** 123456

**In-Person Location:** RDCK Board Room, 202 Lakeside Drive, Nelson, BC

**COMMISSIONERS**

Commissioner Jim Demers	Electoral Area E
Commissioner Dan Gatto	Electoral Area E
Commissioner Marvin Paisner	Electoral Area E
Commissioner Dan Rye	Electoral Area E
Commissioner Karyn Shaundell	Electoral Area E

**COMMISSIONERS ABSENT**

Commissioner Kevin Skarbo	Electoral Area E
---------------------------	------------------

**DIRECTORS**

Cheryl Graham	Electoral Area E, Director
---------------	----------------------------

**STAFF**

Sadie Chezenko	Planning Technician
Zachari Giacomazzo	Planner
Stephanie Johnson	Planner

**PUBLIC**

Holly Pruett	Applicant
Don Pruett	Applicant
Judy Levinson	Applicant
Anonymous member of the public	
Anonymous member of the public	
Anonymous member of the public	

**5 out of 6 voting Commission members were present – quorum was met.**

**1. CALL TO ORDER**

Chair Rye called the meeting to order at 3:05 p.m

**2. TRADITIONAL LANDS ACKNOWLEDGEMENT STATEMENT**

We acknowledge and respect the Indigenous peoples within whose traditional lands we are meeting today.

**3. ADOPTION OF AGENDA**

**MOVED** and seconded,  
AND Resolved:

The Agenda for the May 30, 2024 Electoral Area E Advisory Planning and Heritage Commission meeting, be adopted with the amendment that item 5.1 be moved to 5.2 and 5.2 be moved to 5.1.

**Carried**

**4. RECEIPT OF MINUTES**

The April 25, 2024 Electoral Area E Advisory Planning and Heritage Commission minutes, have been received.

**5. STAFF REPORTS**

**5.1 Development Permit Application – DP2402E – Dustin Lalik**

The Referral Package dated April 22, 2024 from Planner Stephanie Johnson, has been received.

**Moved** and seconded,  
AND Resolved that it be recommended to the Board:

Planner Stephanie Johnson provided a brief overview of the application noting the lack of concerns with the proposal at this stage and that a covenant was registered on title as part of the previous Site Specific Floodplain Exemption (SSFE) application.

The commissioners discussed the following:

- The previous SSFE which was issued and the improvement of the current application over previous proposals

That the Area E Advisory Planning Commission **SUPPORT** the Development Permit Application to Dustin Lalik for the property located 389 Park Ave, Kootenay Lake Village, Proctor and legally described as STRATA LOT 31 DISTRICT LOT 873 KOOTENAY DISTRICT STRATA PLAN NES3286 TOGETHER WITH AN INTEREST IN THE COMMON PROPERTY IN PROPORTION TO THE UNIT ENTITLEMENT OF THE STRATA LOT AS SHOWN ON FORM V

**Carried**

## **5.2 Site-Specific Floodplain Exemption Application – F2302E- Highland Consulting c/o Cooper Husband**

The Referral Package dated May 10, 2024 from Planner Zachari Giacomazzo, has been received.

Planner Zachari Giacomazzo presented a brief overview of the application as well as clarifying the applications required for this type of proposal (SSFE, Watercourse Development Permit and Building Permit) and the order in which these are applied for.

The commissioners discussed the following:

- Inconsistencies with the drawings in the engineers report (applicant clarified that the plans evolved since report was written), the change to site all structures outside of 7.5m from the natural boundary, the specified flood construction levels and the fact that detailed plans and elevation drawings did not exist yet. The Commissioners identified the challenge in giving recommendations without more specific information and one commissioner felt that there was not enough information to support the application.

**Moved** and seconded,

AND Resolved that it be recommended to the Board:

That the Area E Advisory Planning and Heritage Commission **SUPPORT** the Site-Specific Floodplain Exemption Application to Highland Consulting c/o Cooper Husband for the property located 2205 Bealby Road, Rural Nelson and legally described as LOT A DISTRICT LOT 1316 KOOTENAY DISTRICT PLAN NEP85347

**Carried**

## **6. PUBLIC TIME**

The Chair will call for questions from the public at 3:35 p.m.

## **7. NEXT MEETING**

The next Electoral Area E Advisory Planning and Heritage Commission Meeting is scheduled for June 27, 2024.

## **8. ADJOURNMENT**

**MOVED** and seconded,

**AND Resolved:**

The Electoral Area E Advisory Planning and Heritage Commission meeting be adjourned at 3:36 p.m.

**Carried**



# Watercourse Development Permit Application

Referral Form – RDCK File DP2307E

Date: August 9, 2024

**You are requested to comment on the attached DEVELOPMENT PERMIT for potential effect on your agency's interests. We would appreciate your response WITHIN 30 DAYS (PRIOR TO SEPTEMBER 9, 2024). If no response is received within that time, it will be assumed that your agency's interests are unaffected.**

**LEGAL DESCRIPTION & GENERAL LOCATION:**

2205 Bealby Road, Rural Nelson, Electoral Area 'E'  
 LOT A DISTRICT LOT 1316 KOOTENAY DISTRICT PLAN NEP85347 (PID: 027-301-656)

**PRESENT USE AND PURPOSE OF PERMIT REQUESTED:**

The subject property is 0.13 ha in size, and is located between Kootenay Lake and the CP Rail Line approximately 1 km northeast of the City of Nelson.

In the spring of 2023 a significant number of mature trees were removed within the 15 metre development permit area of Kootenay Lake. This application has been submitted for the unauthorized destruction of vegetation, tree removal and also to permit the construction of a new single detached dwelling with a secondary suite and installation of a new wastewater system. The existing cabin will be demolished/removed and the proposed dwelling will be constructed in approximately the same location as the existing cabin.

AREA OF PROPERTY AFFECTED	ALR STATUS	ZONING	OCP
0.13 hectares	n/a	n/a	Official Community Plan Bylaw No. 2260 Country Residential (RC)

**APPLICANT:**

Judith and Jerry Levinson

**OTHER INFORMATION: ADVISORY PLANNING COMMISSION PLEASE NOTE:**

If your Advisory Planning Commission plans to hold a meeting to discuss this Development Permit application, please note that the applicants must be provided with an opportunity to attend such meeting, in accordance with Section 461, subsection (8) of the *Local Government Act*, which reads as follows:

*"If the commission is considering an amendment to a plan or bylaw, or the issue of a permit, the applicant for the amendment or permit is entitled to attend meetings of the commission and be heard."*

**Please fill out the Response Summary on the back of this form. If your agency's interests are 'Unaffected' no further information is necessary. In all other cases, we would appreciate receiving additional information to substantiate your position and, if necessary, outline any conditions related to your position. Please note any legislation or official government policy which would affect our consideration of this permit.**

**ZACHARI GIACOMAZZO, PLANNER  
 REGIONAL DISTRICT OF CENTRAL KOOTENAY**

<input checked="" type="checkbox"/> MINISTRY OF TRANSPORTATION AND INFRASTRUCTURE <input checked="" type="checkbox"/> HABITAT BRANCH (Environment) <input checked="" type="checkbox"/> FRONTCOUNTER BC (MFLNRORD) <input checked="" type="checkbox"/> AGRICULTURAL LAND COMMISSION <input type="checkbox"/> REGIONAL AGROLOGIST <input type="checkbox"/> ENERGY & MINES <input type="checkbox"/> MUNICIPAL AFFAIRS & HOUSING	REGIONAL DISTRICT OF CENTRAL KOOTENAY DIRECTORS FOR: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D <input checked="" type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/> G <input type="checkbox"/> H <input type="checkbox"/> I <input type="checkbox"/> J <input type="checkbox"/> K ALTERNATIVE DIRECTORS FOR: <input type="checkbox"/> A <input type="checkbox"/> B <input type="checkbox"/> C <input type="checkbox"/> D <input checked="" type="checkbox"/> E <input type="checkbox"/> F <input type="checkbox"/> G <input type="checkbox"/> H <input type="checkbox"/> I <input type="checkbox"/> J <input type="checkbox"/> K <input checked="" type="checkbox"/> APHC AREA E <input checked="" type="checkbox"/> CITY OF NELSON FIRE SERVICES <input checked="" type="checkbox"/> RDCK EMERGENCY SERVICES
--	---

<input checked="" type="checkbox"/> INTERIOR HEALTH, HBE TEAM	<input checked="" type="checkbox"/> RDCK BUILDING SERVICES
<input type="checkbox"/> KOOTENAY LAKES PARTNERSHIP (FORESHORE DEVELOPMENT PERMITS)	<input type="checkbox"/> RDCK UTILITY SERVICES
<input type="checkbox"/> SCHOOL DISTRICT NO.	<input type="checkbox"/> RDCK RESOURCE RECOVERY
<input type="checkbox"/> WATER SYSTEM OR IRRIGATION DISTRICT	<input type="checkbox"/> RDCK REGIONAL PARKS
<input checked="" type="checkbox"/> UTILITIES (FORTIS, BC HYDRO, NELSON HYDRO, COLUMBIA POWER)	



The personal information on this form is being collected pursuant to *Regional District of Central Kootenay Planning Procedures and Fees Bylaw No. 2457, 2015* for the purpose of determining whether the application will affect the interests of other agencies or adjacent property owners. The collection, use and disclosure of personal information are subject to the provisions of FIPPA. Any submissions made are considered a public record for the purposes of this application. Only personal contact information will be removed. If you have any questions about the collection of your personal information, contact the Regional District Privacy Officer at 250.352.6665 (toll free 1.800.268.7325), [info@rdck.bc.ca](mailto:info@rdck.bc.ca), or RDCK Privacy Officer, Box 590, 202 Lakeside Drive, Nelson, BC V1L 5R4.

## RESPONSE SUMMARY

**FILE: DP2307E APPLICANT: JUDITH AND JERRY LEVINSON**

**Name:**


**Date:**

**Agency:**

**Title:**

RETURN TO: ZACHARI GIACOMAZZO, PLANNER  
DEVELOPMENT AND COMMUNITY SUSTAINABILITY SERVICES  
REGIONAL DISTRICT OF CENTRAL KOOTENAY  
BOX 590, 202 LAKESIDE DRIVE  
NELSON, BC V1L 5R4  
Ph. 250-352-8190  
Email: [plandept@rdck.bc.ca](mailto:plandept@rdck.bc.ca)

# RDCK Map



Esri Community Maps  
Contributors, Esri Canada,  
Esri, HERE, Garmin,  
SafeGraph,  
GeoTechnologies, Inc,



REGIONAL DISTRICT OF CENTRAL KOOTENAY  
Box 590, 202 Lakeside Drive,  
Nelson, BC V1L 5R4  
Phone: 1-800-268-7325 www.rdck.bc.ca  
maps@rdck.bc.ca

### Legend

- Streams and Shorelines
- Electoral Areas
- RDCK Roads
- Cadastre
- Civic Address

### Map Scale:

1:1,128

Date: March 29, 2023



The mapping information shown are approximate representations and should only be used for reference purposes. The Regional District of Central Kootenay is not responsible for any errors or omissions on this map.

# RDCK Map








Maxar



REGIONAL DISTRICT OF CENTRAL KOOTENAY  
Box 590, 202 Lakeside Drive,  
Nelson, BC V1L 5R4  
Phone: 1-800-268-7325 [www.rdck.bc.ca](http://www.rdck.bc.ca)  
[maps@rdck.bc.ca](mailto:maps@rdck.bc.ca)

## Legend

-  Streams and Shorelines
-  Electoral Areas
-  RDCK Roads
-  Cadastre
-  Civic Address

## Map Scale:


1:1,128

Date: March 29, 2023



The mapping information shown are approximate representations and should only be used for reference purposes. The Regional District of Central Kootenay is not responsible for any errors or omissions on this map.





Levinson WDP | Riparian Assessment | SPEA Setbacks

- Property Boundary (PID 027-301-656)
- Natural Boundary
- WDP Area (15 m)
- LWD ZOS and Litterfall ZOS (15 m)
- Shade ZOS (13 - 28 m)
- SPEA ZOS (15 - 28 m)



Map Date: 08/14/2023  
 Projection: NAD83 UTM Zone 11  
 Project: 2023-1034  
 Map Scale: 1: 500  
 Orthoimage Date: April 20, 2023  
 Fortis BC Lake Level: 530.11 m



2205 Bealby Road, Rural Nelson, BC

## Riparian Assessment V 2.1



Prepared for:

**Regional District of Central Kootenay**

202 Lakeside Drive

Nelson, BC, V1L 5R4

June 12, 2024



Riparian Assessment Report Revision History

Version	Date	Description	Author
1.0	Aug 23, 2023	Report finalized and Submitted to RDCK	Fiona Lau
2.0	April 12, 2024	Report and plans revised and re-submitted to RDCK to reduce development from 2 cabins to one main house.	Fiona Lau
2.1	June 12, 2024	Report revised and re-submitted to RDCK. Added Section 2.2.1.3- Hall Spring description	Fiona Lau

Disclosure Statement

This report has been prepared by Fiona Lau B.Tech., AScT. and reviewed by Ico de Zwart, PChem. RP Bio.

I, Fiona Lau, hereby certify that:

- a) I am a qualified environmental professional (QEP), as defined in the Riparian Areas Regulation made under the Fish Protection Act;
- b) I am qualified to carry out this part of the assessment of the development proposal made by the developer;
- c) I have carried out my assessment of the development proposal, and my assessment is set out in this Assessment Report; and
- d) In carrying out my assessment of the development proposal, I have followed the assessment methods set out in the Schedule to the Riparian Areas Protection Regulation.

This report has been prepared by a QEP who has not acted for, or as an agent(s) of the RDCK and was at the expense of the property owner.

TABLE OF CONTENTS

Table of Contents ..... ii

List of Tables ..... iii

List of Appendices ..... iii

1 Introduction ..... 1

2 Project Overview ..... 2

    2.1 Site Location ..... 2

    2.2 Existing Site Conditions ..... 2

        2.2.1 Watercourses ..... 4

            2.2.1.1 Kootenay Lake ..... 4

            2.2.1.2 Bossuet Creek ..... 5

            2.2.1.3 Hall Spring ..... 5

        2.2.2 Existing Development ..... 5

    2.3 Proposed Development ..... 1

    2.4 Services ..... 1

3 Regulatory Overview ..... 2

    3.1 Kootenay Lake Shoreline Management Guidelines ..... 2

4 Environmental Resources ..... 3

    4.1 Fish and Aquatic Habitat ..... 3

    4.2 Vegetation ..... 4

    4.3 Wildlife ..... 5

        4.3.1 Reptiles and Amphibians ..... 5

        4.3.2 Birds ..... 6

        4.3.3 Mammals ..... 7

    4.4 Species at Risk ..... 7

    4.5 Archeological and Heritage Resources ..... 8

5 Impact Assessment ..... 8

6 Measures to Protect the Integrity of the SPEA ..... 9

    6.1 Scheduling of Environmentally Sensitive Activities ..... 9

    6.2 Danger Trees ..... 9

    6.3 Windthrow ..... 10

    6.4 Slope Stability ..... 10

    6.5 Protection of Trees and Vegetation in the SPEA ..... 10

6.6	Encroachment.....	11
6.7	Sediment and Erosion Control.....	11
6.8	Stormwater Management.....	12
6.9	Floodplain Concerns.....	12
6.10	Protection of Fish and Wildlife Habitat.....	13
6.11	Management of Equipment and Fuel/Lubricant Materials.....	13
6.12	Concrete Management.....	14
6.13	Invasive Plant Management.....	14
7	Mitigation and Monitoring Plan.....	15
8	Conclusion.....	15
9	Closure.....	16
10	References.....	17

LIST OF TABLES

Table 1.	Results of detailed RAPR assessment for Kootenay Lake.....	2
Table 2.	Aquatic and archaeological risk results.....	2
Table 3.	Plant species encountered on the property and adjacent property to southwest.....	5
Table 4.	Species at risk with potential occurrence based on iMap BC 10 km radius query.....	24

LIST OF APPENDICES

- Appendix 1. Location Map
- Appendix 2. Proposed Development Plans
- Appendix 3. Species at risk with potential occurrence based on iMap BC 10 km radius query
- Appendix 4. Archaeological Chance Find Procedure



### 1 INTRODUCTION

Masse Environmental Consultants Ltd. was retained by Judith and Jerry Levinson (Owners) to conduct a riparian assessment to accompany an application for a Watercourse Development Permit (WDP) for their waterfront property located at 2205 Bealby Road, Nelson, BC (PID 027-301-656, Lot A, Plan NEP85347, DL 1316, Kootenay Land District (KLD)). The development permit is required for proposed development within the WDP area that includes the demolition and replacement of an existing residential structure, construction of a one-bedroom cabin and associated septic and water services. It was also triggered by enforcement action from the Regional District of Central Kootenay (RDCK) when unauthorized removal of riparian vegetation was conducted in preparation for this development without a WDP. The Owner is seeking a site-specific floodplain exemption in order to redevelop the property, which involves a relaxation of the floodplain setback from 15 m to 7.5 m, as the property characteristics present a case of serious hardship.

A site visit was completed on April 26, 2023, by Fiona Lau B.Tech., A.Sc.T., Jennifer Ross, M.Sc., P.Chem., and Chanel Gagnon, B.Sc., B.I.T., to conduct a riparian assessment on the property within the 15 m WDP area. The riparian assessment evaluates the existing conditions of the property and riparian areas, identifies habitat values, assesses potential environmental impacts, and recommends measures to mitigate or compensate for the alteration of the riparian area to maintain environmental values. It is based on the following regulatory framework and best management practices documents:

- RDCK Electoral Area 'E' Rural Official Community Plan Bylaw No. 2260, 2013
- RDCK Floodplain Management Bylaw No. 2080, 2009
- British Columbia Riparian Areas Protection Regulation B.C. Reg. 178/2019
- Kootenay Lake Shoreline Management Guidelines
- British Columbia Water Sustainability Act
- British Columbia Wildlife Act
- Federal Fisheries Act
- Federal Migratory Birds Convention Act
- Develop with Care. Environmental Guidelines for Urban and Rural Land Development in B.C.
- Requirements and Best Management Practices for Making Changes In and About A Stream in British Columbia
- A Resource for Kootenay Lake Living – RDCK Kootenay Lake Development Permit Area Resource
- On the Living Edge: Your Handbook for Waterfront Living
- British Columbia FireSmart Homeowners Manual
- A Homeowner's Guide to Stormwater Management

This report has been prepared by Jennifer Ross, M.Sc., P.Chem. and reviewed by Fiona Lau, ASCT.

I, Fiona Lau, hereby certify that:

- e) I am a Qualified Environmental Professional (QEP), as defined in Section 21 of the Riparian Areas Protection Regulation made under the Riparian Areas Protection Act;
- f) I am qualified to carry out this part of the assessment of the development proposal made by Judith and Jerry Levinson which is described in Section 2.3 of this Assessment Report;
- g) I have carried out my assessment of the development proposal, and my assessment is set out in this Assessment Report; and
- h) In carrying out my assessment of the development proposal, I have followed the assessment methods set out in the Minister's technical manual to the Riparian Areas Protection Regulation.

## 2 PROJECT OVERVIEW

### 2.1 Site Location

The subject property is located in Area E of the RDCK, approximately 700 m northeast of the City of Nelson, BC (see Appendix 1 for Location Map). The property is 0.326 acres (0.13 ha) in size, with ~80 m of frontage on Kootenay Lake. It is located at the end of Bealby Road and is bordered by private properties to the north and southwest, Kootenay Lake to the west, and the Canadian Pacific Railway (CPR) to the southeast.

The project area is within the Interior Cedar-Hemlock dry warm variant 1 (ICHdw1) biogeoclimatic subzone, which occurs at valley bottom elevations around most of Kootenay Lake (MacKillop and Ehman 2016). The ICHdw1 subzone is characterized by moist, warm springs, hot and dry summers, and mild, dry winters with moderately shallow snowpack. Winter rain-on-snow events are frequent and snow-free areas are common, particularly on warm-aspect sites. The ICHdw1 is a highly productive biogeoclimatic unit. Common species include: interior Douglas fir (*Pseudotsuga menziesii*), Western red cedar (*Thuja plicata*), Western larch (*Larix occidentalis*), lodgepole pine (*Pinus contorta*), paper birch (*Betula papyrifera*), ponderosa pine (*Pinus ponderosa*), black huckleberry (*Gaylussacia baccata*), falsebox (*Paxistima myrsinites*), Prince's pine (*Chimaphila umbellata*), queen's cup (*Clintonia uniflora*), twinflower (*Linnaea borealis*), and pipecleaner moss (*Robust rhytidiopsis*) (MacKillop and Ehman 2016).

### 2.2 Existing Site Conditions

Given the WDP and floodplain setbacks (both 15 m), the subject property has an eligible developable area of 13 % (184 m<sup>2</sup>) split between the southwest and east corners (Crowsnest Engineering 2023). Based on the site characteristics and the setback requirements, a case of hardship should be considered by the RDCK for the site-specific floodplain exemption and for the proposed development on this property.

## 2205 Bealby Road– Riparian Assessment

Crowsnest Engineering has proposed that the floodplain setback be reduced from 15 m to 7.5 m in order to support re-development of this property.

The property has a northern aspect and is located along the south shore of the West Arm of Kootenay Lake. The topography onsite slopes steeply (1:1 grade) down from the railway and then transitions to a gentle slope (averaging 10 %) into Kootenay Lake.

At the time of the site visit, >90 % of the native riparian vegetation had been impacted by tree falling (Photo 1 and Photo 2). Cleared trees included ~7 mature black cottonwood (*Populus trichocarpa*) trees, 3 mature Douglas maple (*Acer glabrum*) clusters, 2 mature lodgepole pine trees, 1 mature paper birch cluster, and ~12 mature Western redcedar trees (Photo 3 and Photo 4). A total of 25-30 trees were removed from the riparian assessment area with only three trees retained which included two Western redcedars and one lodgepole pine. Some regenerating cottonwood seedlings were also left along the foreshore.



Photo 1. Aerial view of property prior to clearing activities.



Photo 2. Aerial view of property post clearing.



Photo 3. View of cleared trees looking east.



Photo 4. View of cleared trees looking west.

## 2.2.1 Watercourses

There are two mapped watercourses on the property: Kootenay Lake and Bossuet Creek.

### 2.2.1.1 Kootenay Lake

Kootenay Lake borders the subject property along the west boundary; it is a long, narrow and deep lake with a surface area of approximately 400 km<sup>2</sup>. Kootenay Lake's main inflows include the Lower Duncan River to the north and the Kootenay River to the south. It drains through the West Arm into the Kootenay River. Kootenay Lake typically experiences one seasonal water level increase annually, which occurs in the late spring and early summer months (late May through July). Lake levels can vary up to 4 m throughout the year, affecting the extent of exposed shoreline.

The natural boundary of Kootenay Lake was staked along the property line at ~534- 535 m elevation (LTSA 2023; Crowsnest Engineering 2023) by unknown surveyors. The natural boundary line shown on the proposed development plans (Appendix 2) will be used as the HWM from which the streamside protection area setbacks will be determined as per the Riparian Areas Protection Regulation.

“Natural Boundary” means the visible high-water mark of a watercourse where the presence and action of the water are so common and usual, and so long continued in all ordinary years, as to mark on the soil of the bed of the watercourse a character distinct from that of its banks, in vegetation, as well as in the nature of the soil itself, and includes the active floodplain (RDCK 2013).”

## 2205 Bealby Road– Riparian Assessment

### 2.2.1.2 Bossuet Creek

Bossuet Creek (WSC 300-625474-057968) is a 1st order stream with a mapped length of ~1.7 km. It originates on the eastern slopes of the West Arm of Kootenay Lake within the Svoboda Road community and flows northwest into the Kootenay Lake.

Bossuet Creek is mapped within the subject property (Appendix 1), but no evidence of the creek (aside from the presence of a spring (refer to Section 2.2.2) was observed on the property, nor was any evidence of the creek observed along Bealby Road. However, there are three mapped private water licenses on the upper portion of Bossuet Creek (C048794, C100403, C113235). A defined stream channel with flowing water was observed at the Svoboda Road crossing, approximately 500 m upstream of Bealby Road and downstream of the three licensed points of diversion. Based on these findings, it is assumed that Bossuet Creek has either been diverted, or that it flows subsurface by the time it reaches the Bealby Area. It is therefore not considered a “watercourse” within the subject property according to the Area E OCP and Floodplain Management Bylaw definition.

“Watercourse” means any natural or man-made depression with well-defined banks and a bed 0.6 metres (2.0 feet) or more below the surrounding land serving to give direction to a current of water at least six months of the year and/or having a drainage area of two square kilometers (0.8 square miles) or more upstream of the point of consideration (RDCK 2013).”

### 2.2.1.3 Hall Spring

There is spring on the property (Photo 5), mapped as Hall Spring PD27566 which is conveyed via a big-o pipe to Kootenay Lake (Photo 6). The spring currently has no defined stream channel and a watershed area of < 2 km<sup>2</sup>. Once the spring is daylighted (which is proposed as part of the development), stream channel dimensions will be approximately 1 m wide with a channel depth of ~ 0.3 m deep. The spring in its current state and once daylighted does not meet the definition of a “watercourse” under the RDCK Floodplain Management Bylaw, as defined above.

### 2.2.2 Existing Development

Existing development within the riparian assessment area (30 m from the natural boundary of Kootenay Lake) includes a one-bedroom cabin, a travel trailer, and a pump house.

The existing one-bedroom cabin with a raised wooden deck (total footprint ~90 m<sup>2</sup>) is located ~10 m from the “natural boundary” at its southwest corner (Photo 7). The wooden cabin is constructed on concrete footings and has an associated pump-out cement septic tank but no existing septic field or grey water



management. A parking area (~40 m<sup>2</sup>) wraps the eastern corner of the cabin. This parking area was recently widened to accommodate the tree clearing activities.

A travel trailer with wooden deck (footprint ~35 m<sup>2</sup>) was parked near the northern corner of the property (Photo 8). The travel trailer was used for storage and was located on the “natural boundary”.

The wooden pumphouse located next to the cabin (footprint ~8 m<sup>2</sup>) has been constructed on cement blocks and is located ~9 m from the “natural boundary” (Photo 5 and Photo 7). The pumphouse draws water from an intake line installed into Kootenay Lake (Photo 6). A PVC pipe discharges water of an unknown origin to the lake beside the water intake (Photo 6).



Photo 5. View of Hall Spring (abandoned) southwest of pumphouse




Photo 6. View of two discharge pipes and the water intake line.



Photo 7. View of one-bedroom cabin, deck and pumphouse.



Photo 8. View of travel trailer and deck.

### 2.3 Proposed Development

The proposed development within the 15 m WDP area of Kootenay Lake includes:

- Removal of the existing residence and affixed deck (~90 m<sup>2</sup>).
- Removal of the existing travel trailer and affixed deck (~35 m<sup>2</sup>).
- Removal of the existing pumphouse (~8 m<sup>2</sup>).
- Decommissioning and removal of pipes capturing water from Hall Spring. Hall spring will become daylighted.
- Construction of a new main house (55m<sup>2</sup>)
- Construction of walkway and deck (33 m<sup>2</sup>).
- Construction of a Type 3 Septic System (18 m<sup>2</sup>) with two associated septic fields (~117m<sup>2</sup>).

The proposed setback distance for the new residence and one-bedroom cabin is up to 7.5 m from the “natural boundary”, requiring a Site-Specific Floodplain Exemption to permit the proposed works within the 15 m floodplain and a relaxation of the WDP permit area setback. Septic and water service lines shall run along the south property line.

The proposed development footprint will have a total developable area of 223 m<sup>2</sup> compared to the pre-existing development which had a footprint of 133 m<sup>2</sup>, causing a net riparian habitat loss of 90 m<sup>2</sup>.

Refer to Appendix 2 for the Proposed Site Plan.

### 2.4 Services

Domestic water for the new residence and cabin will be extracted from Kootenay Lake. A water service line will be installed approximately at the mid-section of the property along the general alignment of the existing line. This line will be entrenched into the beach substrate to a depth sufficient to prevent freezing during the winter months.

The septic plan includes Type 3 septic system designed by Highland Consulting, which includes a (1,350 L/day flow) treatment system, two concrete pumping tanks (1000 lGal and 750 lGal), and two septic fields (combined area 2.4 m x 22.5m) covered with fill and sloped at 2H:1V around the perimeter (~117 m<sup>2</sup> total field size including slopes), all located within the 15 m setback, and outside of 7.5 m setback. The Type 3 system was required due to the reduced horizontal separation setback from Kootenay Lake as per the Sewerage System Standard Practice Manual Version 3 (Ralston and Payne 2014).

### 3 REGULATORY OVERVIEW

To determine whether the 15 m WDP setback from the High-Water Mark (HWM) of Kootenay Lake aligns with the Riparian Areas Protection Regulation (RAPR) criteria, a detailed assessment of the subject property was conducted to calculate the Streamside Protection and Enhancement Area (SPEA) setbacks. Results for the Zones of Sensitivity (ZOS) and SPEA are presented in Table 1 and Appendix 2.

As per the RAPR, the large woody debris (LWD) and litter ZOS were plotted 15 m inland from the HWM of Kootenay Lake with the shade ZOS plotted 13 m – 28 m from the HWM from Kootenay Lake. The SPEA setback is determined based on the ZOS with the greatest width. Therefore, within the subject property the SPEA from the HWM of Kootenay Lake is 15-28 m.

Table 1. Results of detailed RAPR assessment for Kootenay Lake.

Feature Type	SPVT <sup>1</sup>	Zones of Sensitivity			SPEA <sup>3</sup>
		LWD <sup>2</sup>	Litter fall	Shade	
Kootenay Lake	TR	15 m	15 m	13-28 m	15-28m

<sup>1</sup> SPVT: site potential vegetation type (TR-tree)

<sup>2</sup> LWD- large woody debris

<sup>3</sup> SPEA- streamside protection and enhancement area

#### 3.1 Kootenay Lake Shoreline Management Guidelines

The Kootenay Lake Foreshore Inventory Mapping (FIM) and the Kootenay Lake Shoreline Management Guidelines documents (Schleppe and Cormano 2013, KLP 2020, KLP 2023) were used to help determine site-specific risks for riparian habitat, Ktunaxa Nation cultural values, and archaeological resources along the shoreline. The property is within FIM segment 243.

Table 2. Aquatic and archaeological risk results.

Aquatic Habitat Index Rating (AHI)	Aquatic Sensitivity	Features	Archaeological Risk	Enhanced Engagement Required
Low	Yes	Emergent Vegetation Bossuet Creek	High	Yes

The subject parcel was flagged as high archaeological risk; however, further assessment of archaeological risk is beyond the scope of this report. For further information please consult the Kootenay Lake Shoreline Guidance Document (KLP 2020). Archaeological Chance Find Procedures are provided in Appendix 4.



#### 4 ENVIRONMENTAL RESOURCES

##### 4.1 Fish and Aquatic Habitat

The foreshore of the property is a sloped beach (~10 % gradient) with substrate consisting mostly of coarse sand with a few large boulders (Photo 9) and some fine gravel. Organic debris from the lake delineated the foreshore areas that were typically under water during high water levels. The in-water substrate was mostly saturated, fine silt and sand. Round boulders, cobbles, and some interspersed gravel pockets were present in the southwestern end of the property (Photo 10) and would be inundated at high water.

Fish habitat along this section of foreshore is juvenile rearing habitat and supports freshwater mussels. Cover habitat (boulders and emergent vegetation) for fish is present at the southwestern end of the property at high water (Photo 11). Multiple areas of groundwater emergence were also observed throughout the property, but suitable shore spawning salmonid habitat was not present due to a lack of suitable gravel substrate below late summer water levels. No known kokanee spawning has been reported in this area (KLP 2023).

Kootenay Lake supports a variety of fish species, including several species of regional interest, such as Kokanee (*Oncorhynchus nerka*), Rainbow Trout (*Oncorhynchus mykiss*), Bull Trout (*Salvelinus confluentus*), White Sturgeon (*Acipenser transmontanus*), Westslope Cutthroat Trout (*Oncorhynchus clarki lewisi*), and Burbot (*Lota lota*). Freshwater mussels (*Anodonta* sp.) were observed within the lake adjacent to the subject property (Photo 12); however, a complete mussel survey was not conducted as part of the riparian assessment. There is potential for the presence of a mussel bed in deeper water based on the substrate and the known occurrence of a mussel bed <1 km downstream at Red Sands beach.



Photo 9. View of beach looking south from neighbouring property at low water.



Photo 10. View of beach looking northeast from neighbouring property at low water.



Photo 11. Cover habitat for fish at high water (bounders and emergent vegetation).



Photo 12. Freshwater mussels in shallow water (underwater photo).

#### 4.2 Vegetation

Riparian vegetation on the subject property prior to tree removal activities was a mixed conifer and deciduous forest with mature Western redcedar, black cottonwood, lodgepole pine, and paper birch trees (Photo 13). Understorey vegetation, still somewhat intact, consists of Douglas maple, regenerating black cottonwood, alder (*Alnus* sp.), snowberry (*Symphoricarpos albus*), rose (*Rosa* spp.), pussy willow (*Salix discolor*), tall Oregon grape (*Mahonia aquifolium*), and red osier dogwood (*Cornus sericea*). Table 3 provides a list of riparian vegetation species encountered on the property and on the adjacent undisturbed property to the southwest during the site visit.

The pre-existing multi-canopied forest would have provided high-value habitat supporting the features, functions, and conditions beneficial to fish in Kootenay Lake. These include important wildlife habitat features, addition of large organic debris into or around the lake, shade to moderate water temperatures, leaf litter and insect drop providing food, nutrients, and organic matter to Kootenay Lake, root matrices that stabilize soils and minimize erosion, and a buffer to protect Kootenay Lake from pollution and surface runoff from upstream areas.

The adjacent property to the southwest remains intact (Photo 14) and supports an ecologically diverse and functioning riparian system; however, the majority of the riparian area along this section of Kootenay Lake (Bealby Point Community) has been disturbed by development, and supports only young, landscaped forest with sparse (<10 % tree and shrub cover).



Photo 13. View of cut down riparian vegetation on property.



Photo 14. Riparian shrubs natural shoreline southwest of property.

Table 3. Plant species encountered on the property and adjacent property to southwest.

Common Name	Scientific Name	Common Name	Scientific Name
Trees		Shrubs cont.	
black cottonwood	<i>Populus balsamifera</i>	rose sp.	<i>Rosa</i> spp.
black hawthorn	<i>Crataegus douglasii</i>	Oregon grape	<i>Manhonia aquifolium</i>
Douglas-fir	<i>Pseudotsuga menziesii</i>	Herbaceous	
lodgepole pine	<i>Pinus contorta</i>	common wormwood	<i>Artemisia absinthium</i>
paper birch	<i>Betula papyrifera</i>	false Salomon's seal	<i>Maianthemum racemosum</i>
Western redcedar	<i>Thuja plicata</i>	fragile fern	<i>Cystopteris fragilis</i>
Shrubs		large-leaved avens	<i>Geum macrophyllum</i>
alder	<i>Alnus</i> sp.	meadow buttercup	<i>Ranunculus acris</i>
common snowberry	<i>Symphoricarpos albus</i>	scouring rush	<i>Equisetum</i> spp.
Douglas maple	<i>Acer glabrum</i>	mosses & grasses	
pussy willow	<i>Salix discolor</i>	Submergent Vegetation	
red osier dogwood	<i>Cornus sericea</i>	Eurasian water-milfoil	<i>Myriophyllum spicatum</i>

### 4.3 Wildlife

Wildlife habitat features associated with this ecosystem type (mature black cottonwood and Western redcedar) would have included habitat for a variety of wildlife, including reptiles, songbirds, piciformes (woodpeckers, sapsuckers, flickers, etc.), raptors and mammals.

#### 4.3.1 Reptiles and Amphibians

Reptiles found nearby include northern alligator lizard (*Elgaria coerulea*), western garter snake (*Thamnophis elegans*) and wandering garter snake (*Thamnophis elegans*) (iNaturalist 2023). Garter snakes



are often found in wetland and riparian areas and have high potential to occur on the site. A common gartersnake (*Thamnophis sirtalis*) was observed ~250 m northeast of the property by C.Gagnon and J.Ross (MEC 2023). Northern alligator lizard is typically found in drier habitats on warm aspects that do not occur in the study area.

There is low potential for amphibians to occur onsite, due to lack of suitable habitat and/or connectivity to breeding habitat.

#### 4.3.2 Birds

Birds are well reported in the area and include many species of shorebirds, open water species, songbirds, piciformes, and raptors. The riparian habitat within the subject property (prior to tree clearing) would have provided excellent bird nesting, foraging, and perching habitat. A songbird nest was located in a shrub ~20 m south of the property (Photo 15), multiple cavities were observed in black cottonwood and paper birch trees, also ~20 m west of the property, and an osprey (*Pandion haliaetus*) was observed perching in a cottonwood tree south of the property (Photo 16).

Birds observed and/or heard around the property by Masse Environmental included: American crow (*Corvus brachyrhynchos*), American robin (*Turdus migratorius*), black-capped chickadee (*Parus atricapillus*), Canada goose (*Branta canadensis*), common loon (*Gavia immer*), dark-eyed junco (*Junco hyemalis*), Northern flicker (*Colaptes auratus*), mallard duck (*Anas platyrhynchos*), osprey, song sparrow (*Melospiza melodia*), violet-green swallow (*Tachycineta thalassina*), and yellow-rumped warbler (*Setophaga coronata*).



Photo 15. View of songbird nest south of property.



Photo 16. Osprey and perch trees south of property.

#### 4.3.3 Mammals

Based on knowledge of the area and discussions with the owners, mammals that may use the riparian area within the subject property include American black bear (*Ursus americanus*), American marten (*Martes americana*), Columbia ground squirrel (*Uroditellus columbianus*), cougar (*Puma concolor*), coyote (*Canis latrans*), North American river otter (*Lontra canadensis*), raccoon (*Procyon lotor*), red squirrel (*Tamiasciurus hudsonicus*), roof rat (*Rattus rattus*), striped skunk (*Mephitis mephitis*), white tail deer (*Odocoileus virginianus*), yellow-bellied marmot (*Marmota flaviventris*) and a variety of bat species (*Myotis* spp.).

During the site visit, raccoon tracks were observed on the property (Photo 17). A couple squirrel caches were also observed in the root balls of trees (Photo 18).



Photo 17. Raccoon tracks along foreshore.



Photo 18. Burrow observed on the subject property.

#### 4.4 Species at Risk

BC Conservation Data Center (CDC) occurrence data and critical habitat for Federally listed species at risk were queried within iMap BC (BC 2023), using a 10 km buffer around the center point of the subject property. The query results are presented in Table 4 (Appendix 3). Eight species at risk and/or critical habitat for species at risk were identified within this buffer. The potential occurrence on the property was assessed as likely, possible, unlikely, or very unlikely, according to known species habitat affinities, the habitat profile of the property, and the proximity to mapped occurrences.

Only one of these species was considered to ‘possibly’ occur on the subject property, the Western Screech Owl (*Megascops kennicottii macfarlanei*), which is blue-listed in BC and listed as threatened federally (COSEWIC 2012). The Western Screech Owl utilizes riparian forests, specifically with black cottonwood

wildlife trees present. It is a species that uses cavities and holes excavated by larger woodpeckers for nesting and roosting.

Many bats species, not identified in the CDC occurrence data are blue-listed in BC (e.g.: little brown myotis (*Myotis lucifugus*), Western small-footed myotis (*Myotis ciliolabrum*), and the Yuma myotis (*Myotis yumanensis*)). The little brown myotis is also listed as 'endangered' under the Species At Risk Act. The little brown myotis and the Yuma myotis are expected to have a 'likely' occurrence rating on the subject property. Bat roosting habitat includes tall, live or dead trees with crevices, peeling bark, or cavities.

#### 4.5 Archeological and Heritage Resources

Kootenay Lake is part of the traditional territory of the Ktunaxa, Sinixt and Syilx (Okanagan) First Nations and archaeological evidence is documented at multiple sites along the shoreline and mountain sides of Kootenay Lake. A review of archaeological resources on this property is outside the scope of this report. Archaeological Chance Find Procedures are provided in Appendix 4 for guidance on which protocols to follow in the event of a chance archaeological find, and to ensure that archaeological sites are documented and protected as required for compliance with the BC Heritage Conservation Act.

### 5 IMPACT ASSESSMENT

The impact assessment was based on the impacts of unauthorized works and proposed works within the 15 m WDP area. Impacts include permanent loss of current and potential riparian habitat throughout the property. This impacts the health and productivity of Kootenay Lake and aquatic and terrestrial wildlife.

The unauthorized removal of riparian vegetation has caused:

- Significant reduction to potential additions of large organic debris into or around the lake, reducing nutrient inputs and cover habitat.
- Significant reduction of shade to moderate the water temperature.
- Significant reduction of leaf litter and insect drop inputs to the lake that provide food, nutrients, and organic matter for the organisms inhabiting the lake.
- Significant reduction of high-value habitat for many varieties of birds, small mammals (including bats), and reptiles such as garter snakes.
- Removal of root matrices that stabilize soils and minimize erosion.
- Elimination of the buffer protecting Kootenay Lake from pollution and surface runoff from upstream areas.
- Increased human presence and activity, which decreases wildlife value and increases human-wildlife conflict.

The proposed development within the WDP area will cause a net riparian habitat loss of 90 m<sup>2</sup> which will add to the cumulative impacts along the Kootenay Lake foreshore. In addition, there is potential for the introduction of sediment into Kootenay Lake from disturbed areas and potential disturbance to nesting birds during construction works.

To help mitigate for the temporary loss of ~820 m<sup>2</sup> of riparian habitat; 1020 m<sup>2</sup> will be restored by replanting of native vegetation, habitat complexing, daylighting of Hall Spring and creation of pollinator gardens over the septic fields. The mitigation plan will be submitted as a stand-alone document.

Provided that the recommended mitigation plan and the measures to protect the SPEA (Section 6) are implemented and followed, the negative impacts associated with the unauthorized works and future use of the property will be minimized and the riparian function within the revegetated area be partially restored over time. The permanent loss of mature riparian vegetation along the foreshore cannot be fully mitigated for as the riparian function has been damaged and the proposed mitigation area will take upwards of 75 plus years to restore riparian function to where it was pre-development.

## 6 MEASURES TO PROTECT THE INTEGRITY OF THE SPEA

This section provides measures to protect the integrity of the SPEA (entire property) as described in RAPR, as well as recommended best management practices for development and future use of the property.

### 6.1 Scheduling of Environmentally Sensitive Activities

Demolition and excavation activities, and the installation of the new water intake line should be completed during the low water period for Kootenay Lake (September through early April) in order to minimize the risk associated with the release of deleterious materials into Kootenay Lake. Other mitigation considerations associated with deleterious materials are discussed in Sections 6.7, 6.11 and 6.12.

### 6.2 Danger Trees

Many of the trees formerly considered to be danger trees were removed from the subject property prior to this assessment. Development should take into account the remaining trees, which should be protected. This includes protection of the large Douglas fir tree, <5 m away from the southern property corner. A certified danger tree assessor was not retained as a part of this assessment. Further assessment of potential danger trees is outside the scope of this project.

### 6.3 Windthrow

Assessment of windthrow risk is beyond the scope of this report, and any such assessment should be led by a Registered Professional Forester (RPF). Given that >90 % of the riparian vegetation was recently cut down on this property, windthrow risk to the remaining trees could exist.

### 6.4 Slope Stability

No slope stability hazard indicators were observed during the site visit. Further assessment of geotechnical hazard is beyond the scope of this report, and any such assessment should be led by a P.Geol, or P.Eng.

### 6.5 Protection of Trees and Vegetation in the SPEA

Clearing of vegetation for the proposed work has already been completed. The three remaining trees and one mature black hawthorne located within the 15 m WDP area will be protected from all future development activities. The retention of these remaining trees is important in order to maintain the remaining wildlife values, habitat complexity, and shoreline stability around the site.

The following mitigation measures will be implemented to protect these remaining trees:

- No further clearing of vegetation will be permitted.
- Excavation or ground disturbance will be avoided within the root zone of retained trees. Roots of a mature tree typically extend from 1-3 times the height of a tree from the tree's trunk (far beyond the drip line) and are typically located within the upper 0.30 – 0.40 m of soil (MFLNRORD 2019).
- Avoid any change in the grade, ground level, or ground surface characteristics around these trees. This includes compaction of the soils due to parking underneath the vegetation.
- Ensure that these trees are not damaged during construction, damage includes broken branches, torn bark, or wounds to the trunk.
- Avoid changes to the natural drainage of the property.
- Avoid the introduction and establishment of invasive weed species. The best way to do this is to know where imported soils are coming from and to ensure they are weed-free. Know the common invasive species in the area (CKISS) and removed them if they begin to establish before they go to seed.
- Avoid the introduction of pollutants that could contaminate the soil next to the trees (e.g., fuels and oils leaking from construction vehicles). Refer to Section 6.11 for mitigation measures recommended for fuel and equipment.



## 6.6 Encroachment

The proposed development will encroach into the SPEA up to 7.5 m from the natural boundary of Kootenay Lake. Temporary encroachment up to and beyond the present natural boundary will be required for the installation of the new water intake line.

To delineate development boundaries and protect existing riparian habitat during demolition and construction of the new residence and the associated septic facilities, a snow fence will be installed along the 7.5 m setback line.

Further development beyond that proposed in this report and in the mitigation plan is strongly discouraged. The proposed mitigation plan has been prepared with the goal of preserving as many of the current wildlife values and shoreline stability features as possible, and to promote re-establishment of some of the riparian vegetation.

## 6.7 Sediment and Erosion Control

In order to prevent erosion of the property and to prevent sediment from entering Kootenay Lake, soil disturbance will be minimized as much as possible and exposed soils will be re-vegetated as soon as possible.

The following mitigation measures should be implemented to reduce the risk of sediment input to Kootenay Lake:

- The water line installation will be scheduled during the lower water period for Kootenay Lake (September through early-April). To the extent possible, all other works construction works within the SPEA should also be conducted within this timing window.
- A sediment fence will be installed below the present natural boundary line of Kootenay Lake during construction of any foundations or footings of the new residence and during construction of the septic facilities. Sediment fencing should be properly keyed into the substrate to a minimum depth of 6”.
- Groundwater and surface water coming into the site will be conveyed around any development area where exposed soils are present. The existing spring will be protected from construction activities using a suitable barrier that can effectively exclude the entry of any deleterious material, including soil and/or sediment.
- During construction, activities should be suspended during periods of heavy rain if there is any risk that continued work could result in sediment delivery to Kootenay Lake. Where required, additional mitigation measures, such as sediment fencing, ditching, check dams, or covering soils

may be required to manage turbid wastewater generated by construction or heavy rain events. Turbid wastewater will not be permitted to leave the construction site.

- During the installation of the water intake line visual monitoring of suspended sediment and turbidity in Kootenay Lake should be conducted. If suspended sediment is generated to the extent that it is migrating away from the property (>30 m), works will be modified to reduce the amount of sediment generated and/or erosion and sediment control measures, such as a sediment curtain, will be installed to contain the sediment.
- Soils will be safely stockpiled in a manner that eliminates the possibility of erosion and sediment transport and stockpiles will be located as far away from Kootenay Lake as possible.
- Disturbed soils should be revegetated as soon as possible after construction.

### 6.8 Stormwater Management

The proposed development will result in an increase in the total impervious area of the property. The following mitigation measures will help decrease stormwater impacts:

- Groundwater and surface water coming into the site will be conveyed around any area where disturbed/exposed soils may occur.
- Pervious materials (e.g., gravel) are recommended for driveways, parking areas, and pathways. This minimizes stormwater runoff from impervious materials (e.g., asphalt and concrete), which must be managed using natural hydrologic pathways. Storm water will not be permitted to discharge directly to Kootenay Lake.
- Design roof rainwater collection systems that direct rainwater into suitable landscape features which can absorb and utilize runoff. Roof runoff will not be permitted to discharge directly to Kootenay Lake.
- Stormwater discharges must adhere to the Water Sustainability Act or any other applicable legislation.

### 6.9 Floodplain Concerns

The proposed development is located within the 15 meter floodplain setback and the 536.5 m flood construction level of Kootenay Lake. A flood assessment was completed by Crowsnest Engineering to support a Site-Specific Floodplain Setback Exemption Application for construction of the three “tiny cabins”. The proposal indicates that “permanent encroachment into the floodplain setback for the proposed cabins to no closer than 7.5 m from the Natural Boundary is geotechnically acceptable” (Crowsnest Engineering 2023).

#### 6.10 Protection of Fish and Wildlife Habitat

To minimize disturbance to fish, wildlife, and their habitat, the following measures will be implemented:

- Adhere to sediment, stormwater, equipment, fuel, and concrete management best practices outlined in this report to ensure that there is no release of deleterious materials into Kootenay Lake.
- The best timing for the proposed development is September to early-April when Kootenay Lake water levels are low (Section 6.1).
- To minimize impacts to fish, the Interim Code of Practice for end-of-pipe fish protection screens for small water intakes in freshwater (DFO 2020) should be followed during the replacement of the water intake line. This includes minimizing the diameter of the water intake line, ensuring that a fish screen is placed at the intake, and installing the water line along a path that minimizes the amount of current and future vegetation disturbance.
- Works in and around the remaining trees and shrubs (particularly large trees with cavities and potential bat habitat) should be monitored for nesting birds or bats if works are to be completed during the songbird breeding season (early-April – mid-August) (ECCC 2023b). Monitoring should be completed by a Qualified Environmental Professional (QEP), who will propose measures to protect any active nests, if found.
- Follow the Guidelines for Raptor Conservation during Urban and Rural Land Development in British Columbia (MOE 2013) if any active raptor nests are discovered within 100 m of the subject property. Active raptor nests are legally protected at all times of the year and some inactive nests (ex: Bald Eagle nests) are similarly protected.
- Avoid any modifications to the beach substrate and preserve the remaining foreshore vegetation and boulders, which provide fish habitat during period of inundation.
- Ensure that any power equipment used is well-maintained and leak free.

#### 6.11 Management of Equipment and Fuel/Lubricant Materials

Deleterious substances degrade water quality and affect fish and fish habitat. A spill prevention and emergency response plan should be developed by the development Contractor(s) to minimize the likelihood and impact of a spill of a deleterious substance, such as fuels, oils, and lubricants contained in equipment or vehicles used for construction.

At a minimum, this plan should:

- Ensure that all construction machinery arrives at the property in a clean condition (preferably steam-cleaned), free of fluid leaks, excess oil or grease, mud, and sediment.

- Retain a heavy equipment contractor that can supply equipment using biodegradable hydraulic oil and greases.
- Ensure that each piece of heavy equipment is equipped with its own spill response kit that is appropriate to the types and quantities of fluids stored within. The contents of each kit must be replaced immediately after use.
- Ensure that all equipment operators are familiar with the use of spill kits and their contents.
- Ensure that leaking equipment is removed from the worksite and repaired offsite whenever possible.
- Park, store, and re-fuel all equipment in a designated area as far away from Kootenay Lake as possible and apply secondary containment (e.g. spill trays) to detect, capture, and contain any potential spills or leaks.
- If a spill occurs immediately abate and contained the spill. Report the spill according to the Spill Reporting Regulation and then clean up. Any contaminated material will be removed from the subject property and disposed of, along with any contaminated soils, in compliance with the Regional District of Central Kootenay Resource Recovery Plan and associated bylaws (RDCK 2023).

### 6.12 Concrete Management

Fresh concrete and concrete laden water is caustic (causing elevated water pH) and toxic to aquatic organisms.

To minimize impacts to Kootenay Lake, the following measures will be implemented:

- No concrete, or wastewater that has been in contact with fresh concrete will be disposed of onsite.
- Concrete delivery trucks will either be equipped with a wash water recycling system to capture all wash water used to clean the truck, or a wash water containment bin large enough to capture and contain all wash water will be made available for truck washing.
- Tool washing will occur in a designated wash basin.
- Wash basins should be set aside so that solid material has time to settle and harden. Contents should be disposed of in compliance with Appendix 14.6 of the Standards and Best Practices for Instream Works, (MWLAP 2004).

### 6.13 Invasive Plant Management

Construction activities can potentially increase the prevalence of invasive plant species which can out-compete native riparian vegetation, causing damage to habitat and ecosystem function. The following

mitigation measures are recommended to reduce the establishment and proliferation of invasive plant species on site:

- All equipment should be thoroughly washed and inspected before entering the project site to prevent the import of new invasive plant seeds and root fragments.
- The amount of soil disturbance should be minimized and exposed soils should be re-vegetated immediately following construction.
- Manage new invasive weeds (e.g. hand pulling) on the property according to guidance from the Central Kootenay Invasive Species Society (CKISS) to prevent establishment and spread. Note that no terrestrial priority invasive species were documented during this assessment.
- Eurasian water milfoil (*Myriophyllum spicatum*) is a priority species for the CKISS region that listed for “containment” action. Given that this plant spreads through fragmentation of the plant, containment actions would include avoiding excavation for the new water intake line within areas that are invaded and limiting boats with components (e.g. propellers) that could fragment the plant in invaded areas.

## 7 MITIGATION AND MONITORING PLAN

A separate document for site mitigation and monitoring has been prepared by Masse. Refer to Mitigation and Monitoring Plan (Masse 2023).

## 8 CONCLUSION

Based on the characteristics of the subject property and the setback requirements (15 m for both the WDP and floodplain), only ~13 % (184 m<sup>2</sup>) of the property is available for development and this area is split between the southwest and east corners (Crowsnest Engineering 2023). This presents a case of “serious hardship” and the Owner is requesting a reduction to the floodplain setback and a relaxation of the WDP permit area setback for the proposed development on this property. The proposed setback distance is 7.5 m from the present natural boundary.

Overall, the unauthorized removal of riparian vegetation and the proposed development along the foreshore of Kootenay Lake has and will cause the direct loss of 223 m<sup>2</sup> of high-value riparian habitat within the WDP area. The proposed mitigation plan and the measures to protect SPEA outlined in this report will help mitigate some of the riparian habitat loss; however, the loss of riparian vegetation and proposed development within the SPEA will add to the cumulative impacts along the foreshore.

## 9 CLOSURE

This report has been prepared by a Qualified Environmental Professional (QEP) who has not acted for, or as an agent(s) of the RDCK and was at the expense of the property owner.

I, Fiona Lau, certify that I am qualified to carry out this assessment; and that the assessment methods under the Regulation have been followed; and that, in my professional opinion:

- (i) if the development is implemented as proposed, or
- (ii) if the streamside protection and enhancement areas identified in the report are protected from the development, and
- (iii) if the developer implements the measures identified in the report to protect the integrity of those areas from the effects of the development,

then there will be no harmful alteration, disruption or destruction of natural features, functions and conditions that support fish life processes in the riparian assessment area.

If you have any comments or questions, please do not hesitate to contact the undersigned.

Sincerely,



Fiona Lau, B.Tech., A.Sc.T.

[fiona@masseenvironmental.com](mailto:fiona@masseenvironmental.com)



Jennifer Ross, M.Sc., P. Chem.

Masse Environmental Consultants

## 10 REFERENCES

[BC] Province of British Columbia. 2014. Water Sustainability Act. SBC 2014, Chapter 15, This Act is current to March 29, 2023. Victoria, British Columbia, Canada.

[BC]. 2019. Riparian Areas Protection Regulation. B.C. Reg. 178/2019, Last amended February 5, 2021 by B.C. Reg. 11/2021. Victoria, British Columbia, Canada.

[BC]. 2023. iMap BC Mapping Application. Available online at:  
<https://www2.gov.bc.ca/gov/content/data/geographic-data-services/web-based-mapping/imapbc>

British Columbia FireSmart. N.D. FireSmart BC Homeowner's Manual. Available online at:  
[https://firesmartbc.ca/wp-content/uploads/2021/04/05.31.22.FireSmartBC\\_HomeownersManual\\_Printable.pdf](https://firesmartbc.ca/wp-content/uploads/2021/04/05.31.22.FireSmartBC_HomeownersManual_Printable.pdf)

[COSEWIC] Committee on the Status of Endangered Wildlife in Canada. 2012. COSEWIC Assessment and Status Report on the Western Screech-Owl *kennicottii* subspecies *Megascops kennicottii kennicottii* and the Western Screech-Owl *macfarlanei* subspecies *Megascops kennicottii macfarlanei* in Canada. Committee on the Status of Endangered Wildlife in Canada. Ottawa. xii + 30 pp.

Crowsnest Engineering. 2023. Flood Assessment for Proposed Site-Specific Floodplain Setback Exemption: 2205 Bealby Road. File No.: LEVI-2023-001. Completed by Nicholas Ellis, P. Eng. February 27<sup>th</sup>, 2023.

[DFO] Fisheries and Oceans Canada. 2020. Interim code of practice: End-of-pipe fish protection screens for small water intakes in freshwater. Available online at:  
<https://www.dfo-mpo.gc.ca/pnw-ppe/codes/screen-ecran-eng.html>

[ECCC] Environment and Climate Change Canada. 2023a. Pileated Woodpecker Cavity Identification Guide. Available online at: <https://www.canada.ca/en/environment-climate-change/services/avoiding-harm-migratory-birds/pileated-woodpecker-cavity-identification-guide.html>

[ECCC]. 2023b. General Nesting Periods of Migratory Birds. Available online at:  
<https://www.canada.ca/en/environment-climate-change/services/avoiding-harm-migratory-birds/general-nesting-periods/nesting-periods.html>

## 2205 Bealby Road– Riparian Assessment

Gov BC . 2022. Requirements and Best Management Practices for Making Changes In and About a Stream in British Columbia, V. 2022.01. Government of British Columbia.

Highland Consulting Ltd. 2022. Initial Septic Site Investigation for 2205 Bealby Rd., Nelson, BC. HCL Project #22538. Dated September 16, 2022.

iNaturalist Network. 2023. iNaturalist Interactive Mapping. Available online at:  
<https://www.inaturalist.org/observations>

Kipp, S. and Callaway, C. 2002. On the Living Edge. Your Handbook for Waterfront Living.

[KLP] Kootenay Lake Partnership. 2020. Shoreline Guidance Document – Kootenay Lake. Originally prepared by Ktunaxa Nation Council, Regional District of Central Kootenay, Ministry of Forests, Lands, and Natural Resource Operations, Ecoscape Environmental Consultants Ltd., Tipi Mountain Eco-Cultural Services Ltd. The Firelight Group Ltd., Wayne Choquette.

[KLP]. 2023. Kootenay Lake Shoreline Inventory Mapping Interactive Map. Available online at:  
<http://kootenaylakepartnership.com/>

[LTSA] Land Title and Survey Authority of British Columbia. 2023. ParcelMap BC Mapping Application. Available online at: <https://ltsa.ca/products-services/parcelmap-bc/>

Mackillop, D. and Ehman, A. 2016. A Field Guide to Site Classification and Identification for Southeast British Columbia: the South-Central Columbia Mountains. Province of B.C., Victoria, B.C. Land Management Handbook 70.

[Masse] Masse Environmental Consultants Ltd. 2023. 2309 Bealby Road, Rural Nelson, BC. Riparian Assessment. In preparation.

Metro Vancouver. N.D. A Homeowner’s Guide to Stormwater Management. Available Online at:  
<http://www.metrovancouver.org/services/liquid-waste/LiquidWastePublications/HomeownersGuideStormwaterManagement.pdf>

[MFLNRORD] BC Ministry of Forests, Lands, Natural Resource Operations and Rural Development. 2019. Riparian Areas Protection Regulation Technical Assessment Manual. V 1.1. November 2019.



[MoE] BC Ministry of Environment. 2013. Guidelines for Raptor Conservation during Urban and Rural Land Development in British Columbia (2013). Province of British Columbia. Victoria, British Columbia, Canada.

[MoE] BC Ministry of Environment. 2014. Develop with Care 2014. Environmental Guidelines for Urban and Rural Land Development in British Columbia. Province of British Columbia. Victoria, British Columbia, Canada.

[MoE] BC Ministry of Environment. 2016. Best Management Practices and Guidelines for Bats in British Columbia. Province of British Columbia. Victoria, British Columbia, Canada.

[MWLAP] BC Ministry of Water, Land and Air Protection. 2004. Standards and Best Practices for Instream Works. Province of British Columbia. Victoria, British Columbia, Canada.

Ralston, I. and Payne, M. 2014. Sewerage System Standard practice Manual, Version 3. Prepared for the health Protection Branch of the Ministry of Health in collaboration with the Applied Science and Technologists and Technicians of British Columbia. Dated September 2014.

[RDCK] Regional District of Central Kootenay. 2009. Floodplain Management Bylaw No. 2080, 2009. Last updated December 2019.

[RDCK]. 2013. Electoral Area 'E' Rural Official Community Plan Bylaw No. 2260, 2013. Last updated October 2021.


[RDCK]. N.D. A Resource for Kootenay Lake Living. Available online at:  
[https://www.rdck.ca/assets/Services/Land-Use-and-Planning/Documents/2021-04-20-KLDPA\\_Resource -V5.pdf](https://www.rdck.ca/assets/Services/Land-Use-and-Planning/Documents/2021-04-20-KLDPA_Resource-V5.pdf)

[RDCK]. 2023. Resource Recovery Facilities Regulatory Bylaw No. 2891, 2023.

Schleppe, J. and Cormano, A. 2013. Kootenay Lake Foreshore Inventory, Mapping and Aquatic Habitat Index. Ecoscape Environmental Consultants Ltd. Project File: 12-952. July 2013. Prepared for: Kootenay Lake Partnership & Fisheries and Oceans Canada.


APPENDIX 1. LOCATION MAP

LOCATION MAP – 2205 BEALBY ROAD, RURAL NELSON, BC









APPENDIX 2. PROPOSED SITE PLAN WITH SPEA SETBACKS





Levinson WDP | Riparian Assessment | SPEA Setbacks

-  Property Boundary (PID 027-301-656)
-  Natural Boundary
-  WDP Area (15 m)
-  LWD ZOS and Litterfall ZOS (15 m)
-  Shade ZOS (13 - 28 m)
-  SPEA ZOS (15 - 28 m)



Map Date: 08/14/2023  
 Projection: NAD83 UTM Zone 11  
 Project: 2023-1034  
 Map Scale: 1: 500  
 Orthoimage Date: April 20, 2023  
 Fortis BC Lake Level: 530.11 m

APPENDIX 3. SPECIES AT RISK WITH POTENTIAL OCCURRENCE BASED ON IMap BC 10 KM RADIUS QUERY

Table 4. Species at risk with potential occurrence based on iMap BC 10 km radius query.

Common Name (Scientific Name)	Likelihood of Occurrence on Subject Property	Comment	BC Conservation Status <sup>1</sup>	COSEWIC <sup>2</sup> / SARA <sup>2</sup>
Red-tailed Chipmunk ( <i>Neotamias ruficaudus simulans</i> )	Unlikely	CDC occurrences mapped ~8.4 km southwest of the subject property in forested and logged habitat between Sand and Giveout Creeks (Shape ID: 129556, Occurrence ID: 16128).	Blue	NS
Monardella ( <i>Monardella odoratissima</i> ssp. <i>Discolor</i> )	Unlikely	Subject property is within the CDC shapefile. Historical occurrence mapped in the Nelson area (Shape ID: 7836, Occurrence ID: 1244).	Unknown	NS
Caribou (Southern Mountain Population) ( <i>Rangifer Tarandus</i> pop. 1)	Very unlikely	Historically inhabited the Southern Selkirk Mountains, with mapped critical habitat including the subject property. This population has been extirpated (Shape ID: 10261, Occurrence ID: 3979, Habitat IDs: 21275, 21276, 21277, 21281, 21288, 21289, 21290).	Red	E/T
Painted Turtle (Intermountain – Rocky Mountain Population) ( <i>Chrysemys picta</i> pop.2)	Unlikely	CDC occurrences mapped as close as ~4.5 km southwest of the subject property on the south shore of the West Arm of Kootenay Lake (Shape ID: 96321, Occurrence ID: 12177).	Blue	SC
Western Screech-Owl ( <i>Megascops kennicottii macfarleni</i> )	Potential	CDC historical occurrence mapped ~700 m southwest of the subject property in the Nelson area (Shape ID: 1186, Occurrence ID: 4733).	Blue	T
Western Skink ( <i>Plestiodon skiltonianus</i> )	Unlikely	CDC occurrences mapped as close as ~1.1 km from the subject property on the north side of the West Arm of Kootenay Lake (Shape IDs: 28837, 29940, Occurrence IDs: 6942, 6943).	Blue	SC
Whitebark Pine ( <i>Pinus albicaulis</i> )	Very unlikely	Critical habitat (alpine) mapped as close as 2.8 km from the subject property on both sides of the West Arm of Kootenay Lake (Habitat IDs: 101029, 101220, 101518, 101695, 140407, 140408, 140411, and 140430).	Blue	E
White Sturgeon (Upper Kootenay River Population) ( <i>Acipenser transmontanus</i> pop. 1)	Unlikely	Found in the mainstem of Kootenay Lake, known to use the Creston Delta, Duncan Delta, and Crawford Bay (Shape ID: 1370, Occurrence ID: 4745).	Red	E

<sup>1</sup>Red = Species that is at risk of being lost (extirpated, endangered, or threatened) within British Columbia. Blue = Species considered to be of special concern within British Columbia. <sup>2</sup>(E) Endangered = Facing imminent extirpation or extinction. (T) Threatened = Likely to become endangered if nothing is done to reverse the factors leading to its extirpation or extinction. (SC) Special concern = May become a threatened or an endangered species because of a combination of biological characteristics and identified threats. (NS) No Status. Information sources: British Columbia Conservation Data Centre, and personal sightings.

#### APPENDIX 4. ARCHAEOLOGICAL CHANCE FIND PROCEDURE



## Chance Find Procedures for Archaeological Material

This document provides information on how a developer and/or their contractor(s) can manage for potential archaeological material discoveries while undertaking construction and/or maintenance activities. This document can provide assistance to in-field contractors in the identification of archaeological remains and the procedures to follow if a discovery is made. The discovery of human remains initiates a different course of action and is outlined separately.

Under the provincial *Heritage Conservation Act (HCA)*, archaeological sites that pre-date 1846 are automatically protected whether on public or private land. Protected sites may not be damaged, altered or moved in any way without a Section 12 or 14 Permit as issued through the *HCA*. It is illegal to collect or remove any heritage object from an archaeological site unless authorized to do so under permit.

### **1. Activities occurring outside of known Archaeological Sites:**

When archaeological material is encountered outside of known archaeological site areas work in the vicinity must stop immediately no matter what type of material or feature has been identified. Alteration to an archaeological site can only occur under a Section 12 (Site Alteration Permit) or Section 14 (Heritage Inspection Permit) *Heritage Conservation Act* permit. Such permit applications should be prepared by a professional archaeologist.

If archaeological material is discovered during the course of construction activities:

**1.1 Stop Work:** Halt all work in the area of the discovery and safely secure the area. Contact the project manager or site foreman.

**1.2 Contact an Archaeologist:** An archaeologist should be contacted as soon as possible. For a list of qualified archaeologists in the area, the proponent is directed to the BC Association of Professional Consulting Archaeologists website: [www.bcapa.ca](http://www.bcapa.ca). The proponent may also wish to contact the Ktunaxa Nation Council's Archaeology Technician Nathalie Allard for direction (1-250-426-9549; [nallard@ktunaxa.org](mailto:nallard@ktunaxa.org)).

**1.3 Archaeologist provides guidance:** The archaeologist will direct the proponent on the next courses of action, which will include notifying the Archaeology

Branch and First Nations with interest in the area.

## **2. Activities Occurring within Known Archaeological Site Boundaries:**

Land altering activity within a previously recorded archaeological site must be conducted under a Section 12 HCA Site Alteration Permit (SAP), in some cases with an onsite archaeological monitor. It is common for additional archaeological material and features to be encountered during activities occurring within previously recorded archaeological sites. Minor finds (lithic flakes, diffuse charcoal or fire altered rock) may not require work to stop, however significant finds require a level of assessment by a professional archaeologist, and it is up to the onsite project manager to determine the level of significance based on criteria presented below.

### **2.1 Significant Cultural Finds that Require a Professional Archaeologist (described in detail in Section 4)**

- Intact archaeological features, which can include but are not limited to hearths, cultural depressions (e.g. cache pits, house depressions) and rock alignments or forms (e.g. tipi rings, cairns, blinds)
- Significant archaeological materials, which include but are not limited to, the presence of formed lithic tools (e.g. projectile point, microblade core, scraper), a dense concentration of lithic waste flakes, or artistic items
- Human Remains (described in detail in Section 3)

### **2.2 Archaeological Site Management Options**

- 2.2.1 **Site Avoidance:** If the boundaries of a site have been delineated, redesign the proposed development to avoid impacting the site. Avoidance is normally the fastest and most cost effective option for managing archaeological sites. Site avoidance could also be achieved through minimizing ground disturbance by looking for alternative constructive methods.
- 2.2.2 **Mitigation:** If it is not feasible to avoid the site through project redesign, it is necessary to conduct systematic data collection and analysis within the site prior to its loss. This could include surface collection and/or excavation. This work can be time-consuming and therefore expensive to conduct.
- 2.2.3 **Protection:** It may be possible to protect all or portions of the site which will be impacted through installation of barriers during the development period and possibly for a longer period of time. Methods for barrier construction could include fencing around site boundaries or applying

geotextile to the ground surface and capping it with fill. The exact method used would be site-specific.

### **3. Chance Find Procedures for Identified Human Remains**

Procedures in the event of the discovery of human remains during construction are covered in depth by an Archaeology Branch Policy Statement, found on their website at [www.for.gov.bc.ca/archaeology](http://www.for.gov.bc.ca/archaeology), and are summarized below.

- 3.1 Stop all construction activities immediately in the area of found or suspected human remains and contact the RCMP and/or Office of the Coroner.
- 3.2 The coroner must determine whether the remains are of contemporary forensic concern or archaeological/aboriginal.
- 3.3 If the remains are found to be of aboriginal ancestry then the next step involves the relevant First Nations collaboratively determining the appropriate treatment of those remains.

The key to respectfully dealing with ancient aboriginal remains is to involve the appropriate First Nations as early as possible in the process. However this must be done in a manner that does not interfere with the coroner's office ability to conduct their business in the manner that they see fit.

### **4. Site Identification Guide**

The following are characteristics typical to site types found within the Ktunaxa Traditional Territory.

#### **4.1 Artifact Scatters**

Lithic (stone) scatters from the production and maintenance of stone tools are the most common type of archaeological site found in the region. Other materials that may be represented in artifact scatters are Fire Broken Rock (FBR), bone, antler and tooth.

Lithics: What to look for




Image 1: Basic flake morphology



Image 2: Examples of lithic flakes




Image 3: Example of lithic scatter found on ground surface



Image 4: Example of formed lithic artifacts

*Zakōqnuuk*

*Zaqam*

*Lower Kootenay*

*Tobacco Plains*




Image 5: Ground stone artifacts

Bone, Tooth and Antler Artifacts: What to Look For

- Obvious shaping
- Incising
- Unnatural holes



*ᑕᓕᓐᓂᓂᓂᓂ*

*ᑕᓕᓂᓂ*

*Lower Kootenay*

*Tobacco Plains*



## Image 6: Bone and Antler artifacts

### 4.2 Fire Broken Rock and Hearths

Fire-broken rock (FBR) results from the use of fire during cooking, heating and processing activities. FBR is often associated with other features including hearths and cultural depressions, but can also be thinly scattered in concentrations away from the features with which they were first associated.

When looking for FBR, note concentrations of roughly fractured rock from rapid heating and cooling, rock showing signs of burning or oxidation and/or reddening or blackening of surrounding matrix.




Image 7: Example of FBR; note the zig/zag pattern of breakage common to FBR. A hearth feature is evidence of a fire pit or other fireplace feature of any period. Hearths were used for cooking, heating, and processing of some stone, wood, faunal, and floral resources and may be either lined with a wide range of materials like stone or left unlined. Occasionally site formation processes (e.g., farming or excavation) deform or disperse hearth features, making them difficult to identify without careful study.

Hearths: What to look for

- FBR
- reddening or blackening of the associated soil/sediment
- charcoal
- layering of FBR and charcoal, and
- depressions in the earth associated with FBR, reddened or blackened matrix and charcoal.



Image 8: Example of a hearth uncovered along the wall of an excavation unit

#### 4.3 Cultural Depressions

Any depression seen on the ground surface that appears to have been excavated by man can be a cultural depression and have archaeological significance. These “pits” were dug for a variety of reasons such as for food storage, cooking or as a base for a dwelling.

They can range in size from 1m across to 7-10m across, and are usually found associated with other artifacts such as FBR and lithic scatters.

To identify a cultural depression, look for:

- Subtle to deep scours on the ground surface that are circular to rectilinear in shape
- A raised rim along the edge of a depression
- Depressions associated with artifacts and FBR
- Depressions associated with fire reddening and blackening of the matrix





Image 9: Example of a large cultural depression in a natural setting

#### 4.6 Rock Alignments

There are several types of rock alignments that occur within the culture area, which include tipi rings, medicine wheels, cairns and blinds. When attempting to identify rock alignments, look for a group of rocks that look purposefully placed as in a circle, pile or line; isolated groups of rock that do not seem to belong to that landscape; and/or rocks which form a pattern.



Image 10: Example of a Cairn or piling of rocks



Image 11: Example of a tipi ring in a natural setting

*Takisqnuuk*

*Taqam*

*Lower Kootenay*

*Tobacco Plains*



2205 Bealby Road, Rural Nelson, BC

## Mitigation and Monitoring Plan V2.0



Prepared for:

**Regional District of Central Kootenay**

202 Lakeside Drive

Nelson, BC, V1L 5R4

April 12, 2024

Prepared by:  
Masse Environmental Consultants  
812 Vernon Street  
Nelson, BC, V1L 4G4

Project Number 2023-1034

TABLE OF CONTENTS

Table of Contents ..... i

List of Tables ..... i

List of Appendices ..... i

1 Introduction ..... 1

2 Impact Assessment Overview and Mitigation Plan Strategy ..... 1

3 Habitat Complexing ..... 2

4 Revegetation Prescription ..... 2

    4.1 Recommended Plant Species..... 3

        4.1.1 Area 1- Riparian Revegetation ..... 3

        4.1.2 Area 2 -Hall Spring Revegetation..... 4

        4.1.3 Area 3 - Pollinator Gardens..... 5

    4.2 General Planting and Maintenance Guidelines ..... 5

    4.3 Environmental Monitoring ..... 6

5 References ..... 8

LIST OF TABLES

Table 1. Revegetation Plan Prescription..... 3

Table 2. Recommended plant species for site-wide revegetation..... 3

Table 3. Recommended plant species for Hall Spring revegetation. .... 4

Table 4. Native Pollinator Seed Mixture for Septic Field..... 5

LIST OF APPENDICES

- Appendix 1. Mitigation Plan Drawing
- Appendix 2. Complete List of Recommended Species for Revegetation



### 1 INTRODUCTION

On behalf of Judith and Jerry Levinson (Owners), Masse Environmental Consultants Ltd. (Masse) has prepared this Revegetation Plan to accompany the Riparian Assessment Report prepared for 2205 Bealby Road, Rural Nelson, BC. Both documents form the principal components of a Watercourse Development Permit (WDP) Application for unauthorized works and proposed development within the WDP area of Kootenay Lake. Unauthorized works included the removal of mature riparian forest in preparation for the proposed development, which includes the demolition and replacement of an existing residential structure, its associated septic facilities, and the associated water intake from Kootenay Lake; and construction of an additional one-bedroom cabin.

The Mitigation Plan provides the details and prescriptions recommended for helping to restore the ecological values of the property (to the extent possible) following development. It is designed to be used in conjunction with the Riparian Assessment Report and does not aim to repeat the information presented in that document unless to simplify or clarify a mitigation measure or best management practice.

### 2 IMPACT ASSESSMENT OVERVIEW AND MITIGATION PLAN STRATEGY

All of the unauthorized works and >90 % of the proposed development have occurred or will occur within the WDP area and the Streamside Protection and Enhancement Area (SPEA) according to the Riparian Areas Protection Regulation (RAPR) criteria (MFLNRORD 2019). Refer to Appendix 2 of the Riparian Assessment Report for the SPEA Map and Proposed Site Plan.

The Shoreline Management Guidelines for Kootenay Lake (KLP 2020) outlines general principles for shoreline development in order to achieve a “No Net Loss” of habitats present. The principle is achieved by applying the following priority sequence of mitigation options: 1. Avoidance of environmental impacts; 2. Minimization of unavoidable impacts; 3. On-site restoration of unavoidable impacts; and 4. Compensation for residual impacts.

Given the small size of the property and that unauthorized works have already occurred, it is not possible to achieve a “No Net Loss” development plan. This Mitigation Plan therefore focuses on onsite restoration of impacted areas. To help mitigate for the temporary loss of ~820 m<sup>2</sup> of riparian habitat; 1020 m<sup>2</sup> (Ratio (~1.2:1)) will be restored by replanting of native vegetation, habitat complexing, daylighting of Hall Spring and creation of pollinator gardens over the septic fields.

Provided that the recommendations in this plan and the measures to protect the SPEA outlined in the Riparian Assessment Report are implemented and followed, the negative impacts associated with the

unauthorized works, proposed development, and future use of the property will be minimized and the riparian function within the revegetated areas will be partially restored over time. However, the permanent loss of mature riparian vegetation along the foreshore cannot be fully mitigated for as the riparian function has been damaged and the proposed mitigation area will take upwards of 75 plus years to restore riparian function to where it was pre-development.

### 3 HABITAT COMPLEXING

Habitat complexing will involve the daylighting of Hall Spring and placement of large woody debris (LWD) within the riparian area.

Daylighting of Hall Spring will involve the decommissioning and removal of the Big “O” pipes, construction of a shallow gravel/cobble lined channel (~1.0 m wide and 0.3 m deep; Figure 1) and revegetation along the channel is described in Section 4.1.2.




Figure 1. Cross Section of Hall Spring Channel Profile

Prior to revegetation activities commencing, salvaged large woody debris from clearing activities will be scattered around the revegetation area at the direction of the QEP.

### 4 REVEGETATION PRESCRIPTION

The proposed revegetation is designed with a focus on naturalizing the foreshore and creating a vegetation buffer between the development and foreshore area. The revegetation prescription includes three specific planting areas: Riparian, Hall Spring and Pollinator Gardens.

Revegetation will include planting of 32 native trees and a variety of native and ornamental shrubs, forbes, grasses and sedges along the foreshore of Kootenay Lake. Quantities of plant species will be determined by the QEP once development is complete and natural re-establishment of native vegetation has been



assessed. Refer to Appendix 1 for the Proposed Site Plan. Revegetation prescriptions are outlined in Table 1.

Table 1. Revegetation Plan Prescription

Restoration Area	Size (m <sup>2</sup> )	Prescription
Area 1: Riparian	~893	<ul style="list-style-type: none"> <li>Retain topsoil and existing plants to promote natural regeneration of the species remaining in this area.</li> <li>Additional topsoil placement will be required in some areas to support replanting<sup>1</sup>.</li> <li>Plant 26 trees and a mixture of shrubs, perennials, and grasses<sup>2</sup> between existing plants (Table 2).</li> </ul>
Area 2: Hall Spring	~10	<ul style="list-style-type: none"> <li>Retain topsoil and existing plants to promote natural regeneration of the species remaining in this area.</li> <li>Plant a mixture of perennials, sedges and rushes<sup>2</sup> along the spring channel (Table 3).</li> </ul>
Area 3: Pollinator Gardens	~117	<ul style="list-style-type: none"> <li>Apply 3" of premium topsoil over the septic field area and spread pollinator-friendly wildflowers seed mix at a rate of 500 seeds/m<sup>2</sup> (Table 4).</li> </ul>

<sup>1</sup> Topsoil volume and placement to be determined by QEP once residential development is complete.

<sup>2</sup>.Quantities of plants will be determined by the QEP once residential development is complete.

#### 4.1 Recommended Plant Species

##### 4.1.1 Area 1- Riparian Revegetation

A list of trees, shrubs, forbes, and grasses that will be used for site-wide revegetation is provided in Table 2. This list was developed in consultation with the Owners with the goal of incorporating native riparian species with high ecological value back into the property. Plant selection will be dependent on nursery stock and species availability and may be substituted with approval from the QEP. Alternative species that may be substituted are listed in Appendix 2.

Table 2. Recommended plant species for site-wide revegetation.

Common Name	Latin Name	Suggested Pot Size (for planting)
Trees		
Douglas maple	<i>Acer glabrum</i>	5 gallon
lodgepole pine	<i>Pinus contorta</i>	5 or 10 gallon
White pine	<i>Pinus monitocola</i>	5 or 10 gallon
paper birch	<i>Betula papyrifera</i>	5 gallon
water birch	<i>Betula occidentalis</i>	5 gallon
Western red cedar	<i>Thuja plicata</i>	5 or 10 gallon
Shrubs		
common lilac	<i>Syringa vulgaris</i>	TBD

Common Name	Latin Name	Suggested Pot Size (for planting)
dappled willow	<i>Salix integra</i> 'Hakuro Nishiki'	TBD
Oakleaf hydrangea	<i>Hydrangea quercifolia</i>	TBD
mallow ninebark	<i>Physocarpus malvaceus</i>	1 gallon
mock orange	<i>Philadelphus</i> sp.	1 gallon
nootka rose	<i>Rosa nutkana</i>	1 gallon
red-flowering currant	<i>Ribes sanguineum</i>	1 gallon
Red osier dogwood	<i>Cornus stolonifera</i>	1 gallon
sandbar willow	<i>Salix exigua</i>	1 gallon
smoke bush	<i>Cotinus coggygria</i>	TBD
snowberry	<i>Symphoricarpos albus</i>	1 gallon
Forbes		
shrubby penstemon	<i>Penstemon fruticosus</i>	1 gallon
Grasses		
Elijah blue fescue	<i>Festuca glauca</i>	1 gallon
Karl foerster feather reed grass	<i>Calamagrostis acutiflora</i>	1 gallon

These species were selected based on their suitability for the property (ecoregion, exposure, and moisture regime) and based on the following resources:

- Conservation, Restoration and Stewardship of Low Elevation Brushland (GB), Grassland (Gg) and Dry Forest Ecosystems in the West Kootenay Region (McKenzie and Hill 2023).
- British Columbia FireSmart Landscaping Guide
- Invasive Species Council of BC Grow Me Instead Guide
- The EcoGarden Project Plant List for West Kootenay Gardens (CKISS N.D.)
- Riparian Factsheet No. 6 – Riparian Plant Acquisition and Planting (Ministry of Agriculture 2012).
- Pollinator planting guide for the Columbia Mountains and Highlands Ecozone (the David Suzuki Foundation Butterflyway Project)
- A Resource for Kootenay Lake Living

#### 4.1.2 Area 2 -Hall Spring Revegetation

Hall Spring PD27566 is an abandoned and daylighted spring on the property. It discharges water to Kootenay Lake via an underground big-o pipe. Moisture-tolerant forbes, sedges and rushes will be planted along and within the Hall Spring Channel. Refer to Table 3. Recommended plant species for Hall Spring revegetation. for recommended species.

Table 3. Recommended plant species for Hall Spring revegetation.

Common Name	Latin Name	Suggested Pot Size (for planting)
Baltic rush	<i>Juncus balticus</i>	4"
Columbian sedge	<i>Carex aperta</i>	4"
fairybells	<i>Prosartes</i> spp.	4"

Common Name	Latin Name	Suggested Pot Size (for planting)
foamflower	Tiarella trifoliata	4"
Kellogg's sedge	Carex lenticularis	4"
lady fern	Athyrium filix-femina	1 gallon
oak fern	Gymnocarpium dryopteris	1 gallon
thick headed sedge	Carex Pachysyachya	4"
twinflower	Linnaea borealis	4 "

#### 4.1.3 Area 3 - Pollinator Gardens

KinSeed Ecologies was consulted in order to assemble a species list of pollinator-friendly native wildflowers that would be suitable for revegetating a sand mound septic field with a north to northwest aspect, natural seepage in the area, and tolerance to some amount of shade. The recommended species are provided in Table 4. KinSeed Ecologies assists with ecological gardening and restoration in the West Kootenays and provides custom seed mixes for sowing made from seeds that originate in the Kootenays.

Table 4. Native Pollinator Seed Mixture for Septic Field

Common Name	Latin Name	Common Name	Latin Name
autumn sunshine	Helenium autumnale	pink fairies	Clarkia pulchella
brown-eyed Susan	Gaillardia aristata	scarlet gilia	Ipomopsis aggregata
common harebell	Campanula rotundifolia	showy daisy	Erigeron speciosus
golden-aster	Heterotheca villosa	silverleaf phacelia	Phacelia hastata
golden tickseed	Coreopsis tintoria	spikelike goldenrod	Solidago simplex
grand collomia	Collomia grandiflora	threadleaf phacelia	Phacelia linearis
Lewis blue flax	Linum lewisii	yarrow	Achillea millefolium
narrow-leaved skullcap	Scutellaria angustifolia	yellow penstemon	Penstemon confertus

#### 4.2 General Planting and Maintenance Guidelines

- Final plant selection and quantities shall be completed in consultation with the QEP.
- Planting should not occur during periods of hot dry weather unless they are irrigated daily.
- Avoid disturbance of existing plant roots established within the revegetation area.
- Trees shall be planted at >2.5 m spacing, shrubs shall be planted at >0.5m spacing and forbes and grasses shall be planted at >0.25m spacing.
- Locally adapted native plants are preferable to those collected or grown outside the region. The species listed in Table 2 and Table 3 are available from Sagebrush Nursery in Oliver <https://sagebrushnursery.com> .
- Planting holes shall be a minimum of 3 times the size of the pot, unless they are plugs.
- Mix in 25% compost with native soils into each planting hole.
- Specific locations of plants shall be directed by a QEP or landscaper.

- Use transplant fertilizer (i.e. Mykes Mycorrhizae Tree and Shrub or similar), bone meal and blood meal mix as per manufacturers specifications in each planting hole.
- Plantings which do not survive should be replaced to ensure complete establishment of native plants, and exclusion of exotic plants.
- Ensure the objective of the restoration is to naturalize the riparian area and not create a landscaped garden.
- Regularly irrigate new plantings during the plant establishment period for a minimum of 5 years and thereafter as required.
- Pull any invasive weeds on a yearly basis prior to going to seed.
- Replanting of riparian vegetation around buildings should adhere to principles of rural residential fire protection (for more information see the FireSmart Homeowner's Manual MFLNRO N.D.).

### 4.3 Environmental Monitoring

The anticipated effort for environmental monitoring and professional guidance on this project includes the following:

- QEP will be onsite for a pre-construction meeting with Owner and Landscaper to ensure that all parties are aware of environmental sensitivities and familiar with the proposed mitigation measures.
- QEP to provide guidance during revegetation, as required.
- QEP will conduct a post construction site visit once development and revegetation is complete to assess compliance and completion of the project and submit an environmental summary report to the RDCK.
- QEP will conduct interim effectiveness monitoring inspections annually for a three-year period and provide recommendations to the Owner as required.
- A post inspection report will be prepared by the QEP after three growing seasons and submitted to the Owner and RDCK. The following indicators of success of riparian plantings should be documented in this report:
  - Plant composition includes mostly native trees and shrubs.
  - Establishment of >80% of planted riparian species after 3 full years would be a reasonable indication that the mitigation plan has been successfully completed.

2205 Bealby Road– Mitigation Plan

Sincerely,



Fiona Lau, BTech., AScT.

[fiona@masseenvironmental.com](mailto:fiona@masseenvironmental.com)



Jennifer Ross, M.Sc., P. Chem.

Masse Environmental Consulta

## 5 REFERENCES

British Columbia FireSmart. N.D. FireSmart BC Landscaping Guide. Available online at:  
[https://firesmartbc.ca/wp-content/uploads/2021/04/FireSmartBC\\_LandscapingGuide\\_Web\\_v2.pdf](https://firesmartbc.ca/wp-content/uploads/2021/04/FireSmartBC_LandscapingGuide_Web_v2.pdf)

[CKISS] Central Kootenay Invasive Species Society. N.D. The EcoGarden Project for West Kootenay Gardens. Available online at: <https://ckiss.ca/ecogarden-project/>

[ISCBC] Invasive Species Society of BC. 2023. Grow Me Instead Guide. Available Online at:  
<https://bcinvasives.ca/play-your-part/plantwise/grow-me-instead/>

[KLP] Kootenay Lake Partnership. 2020. Shoreline Guidance Document – Kootenay Lake. Originally prepared by Ktunaxa Nation Council, Regional District of Central Kootenay, Ministry of Forests, Lands, and Natural Resource Operations, Ecoscape Environmental Consultants Ltd., Tipi Mountain Eco-Cultural Services Ltd. The Firelight Group Ltd., Wayne Choquette.

McKenzie, E. and Hill, T. 2023. Conservation, Restoration and Stewardship of Low Elevation Brushland (Gb), Grassland (Gg) and Dry Forest Ecosystems in the West Kootenay Region – Background Information Document. Prepared for the Okanagan Nation Alliance and the Fish & Wildlife Compensation Program (FWCP) Section of the Ministry of Forests, Lands, Natural Resource Operations & Rural Development, Nelson, BC. February 28, 2023. 69 pp.


[MFLNRORD] BC Ministry of Forests, Lands, Natural Resource Operations and Rural Development. 2019. Riparian Areas Protection Regulation Technical Assessment Manual. V 1.1. November 2019.

[MoA] BC Ministry of Agriculture. 2012. Riparian Factsheet No. 6. Riparian Plant Acquisition and Planting. Order No. 810.210-6.







[RDCK]. N.D. A Resource for Kootenay Lake Living. Available online at:  
[https://www.rdck.ca/assets/Services/Land-Use-and-Planning/Documents/2021-04-20-KLDPA\\_Resource-V5.pdf](https://www.rdck.ca/assets/Services/Land-Use-and-Planning/Documents/2021-04-20-KLDPA_Resource-V5.pdf)



APPENDIX 1. MITIGATION PLAN DRAWING



Levinson WDP | Riparian Assessment | SPEA Setbacks

-  Property Boundary (PID 027-301-656)
-  Natural Boundary
-  WDP Area (15 m)
-  LWD ZOS and Litterfall ZOS (15 m)
-  Shade ZOS (13 - 28 m)
-  SPEA ZOS (15 - 28 m)



Map Date: 08/14/2023  
 Projection: NAD83 UTM Zone 11  
 Project: 2023-1034  
 Map Scale: 1: 500  
 Orthoimage Date: April 20, 2023  
 Fortis BC Lake Level: 530.11 m

APPENDIX 2. COMPLETE LIST OF RECOMMENDED ALTERNATIVE SPECIES FOR REVEGETATION

Common Name	Latin Name	Sun/Shade	Water Requirement
Trees			
Douglas maple	<i>Acer glabrum</i>	fs-psh	low
lodgpole pine	<i>Pinus contorta</i>	fs	low
water birch	<i>Betula occidentalis</i>	fs-psh	high
Western red cedar	<i>Thuja plicata</i>	fs-psh	medium
Shrubs			
Red alder	<i>Alnus rubra</i>	fs-psh	medium
Baldhip rose	<i>Rosa gymnocarpa</i>	fs-psh	low
Beaked hazelnut	<i>Corylus cornuta</i>	fs-psh	low
birch-leaved spirea	<i>Spiraea betulifolia</i>	fs	low
black huckleberry	<i>Vaccinium membranaceum</i>	fs-psh	low-medium
Common juniper	<i>Juniperus communis</i>	fs-psh	low
common lilac	<i>Syringa vulgaris</i>	fs-psh	low
Common ninebark	<i>Physocarpus opulifolius</i>	fs-psh	low
common snowberry	<i>Symphoricarpos albus</i>	fs-psh	low
elderberry	<i>Sambucus spp.</i>	fs-psh	low
falsebox	<i>Paxistima myrsinites</i>	fs-psh	low
fragrant sumac	<i>Rhus aromatica</i>	fs-psh	very low
Oakleaf hydrangea	<i>Hydrangea quercifolia</i>	fs-psh	medium
kinnikinnick	<i>Arctostaphylos uva-ursi</i>	fs-psh	very low
mallow ninebark	<i>Physocarpus malvaceus</i>	fs-psh	low
mock orange	<i>Philadelphus lewisii</i>	fs-psh	low
nootka rose	<i>Rosa nutkana</i>	fs-psh	low
oceanspray	<i>Holodiscus discolor</i>	fs-psh	medium
Oregon grape	<i>Mahonia spp.</i>	fs-psh	low
potentilla	<i>Potentilla fruticosa</i>	fs-psh	low
red-flowering currant	<i>Ribes sanguineum</i>	fs-psh	medium
Purple spirea/hardhack	<i>Spiraea douglasii</i>	fs-psh	medium
Red osier dogwood	<i>Cornus stolonifera</i>	fs	low
sandbar willow	<i>Salix exigua</i>	fs-psh	high
saskatoon	<i>Amelanchier alnifolia</i>	fs-psh	low
shrubby penstemon	<i>Penstemon fruticosus</i>	fs	low
smoke bush	<i>Cotinus coggygria</i>	fs	low
Smooth sumac	<i>Rhus glabra</i>	fs-psh	low
soopolallie	<i>Shepherdia canadensis</i>	fs	low
thimbleberry	<i>Rubus parviflorus</i>	fs-psh	medium
Wood's rose	<i>Rosa woodsii</i>	fs-psh	medium
Forbes			
Canada goldenrod	<i>Solidago canadensis</i> or <i>lepada</i>	fs	low
common camas	<i>Camassia quamash</i>	fs	medium
Douglas's aster	<i>Symphyotrichum subspicatum</i>	fs	medium
fireweed	<i>Chamerion augustifolium</i>	fs-psh	low
Hairy false Golden aster	<i>Heterotheca villosa</i> ???	fs-psh	low
lamb's ear	<i>Stachys byzantina</i>	fs	low
Large-leaved lupine	<i>Lupinus polyphyllus</i>	fs-psh	medium
Butterfly milkweed	<i>Asclepias tuberosa</i>	fs-psh	low
nodding onion	<i>Allium cernuum</i>	fs-psh	low
showy daisy	<i>Erigeron speciosus</i>	fs-psh	low
silky lupine	<i>Lupinus sericea</i>	fs-psh	low

Common Name	Latin Name	Sun/Shade	Water Requirement
pearly everlasting	<i>Anaphalis margaritacea</i>	fs	low
purple coneflower	<i>Echinacea purpurea</i>	fs-psh	medium
pussytoes	<i>Antennaria</i> spp.	fs-psh	low
spreading dogbane	<i>Apocynum androsaemifolium</i>	fs-psh	low
sticky geranium	<i>Geranium viscosissimum</i>	fs-psh	low
twinflor	<i>Linnaea borealis</i>	fs-psh	medium-high
Wild sarsaparilla	<i>Aralia nudicaulis</i>	fs-psh	medium
wild strawberry	<i>Fragaria virginiana</i>	fs-psh	low-medium
Grasses			
fescues	<i>Festuca</i> spp.	fs-psh	variable
Pine grass	<i>Calamagrostis rubescens</i>	fs-psh	low



## 18.0 DEVELOPMENT PERMIT AREAS

### Background

The OCP may designate Development Permit Areas under the authority of local government legislation. Unless otherwise specified, a development permit must be approved by the Regional Board, or delegate of the Board, prior to any development or subdivision of land within a designated Development Permit Area.

Development Permit Areas allow for implementation of special guidelines for the protection of the natural environment, protection from hazardous conditions, for revitalization of designated areas, or to guide the form and character of development within the Plan area. Development Permit Areas can also be used to meet targets for carbon emission reductions and energy and water conservation.

Where land is subject to more than one Development Permit Area designation, a single development permit is required. The application will be subject to the requirements of all applicable Development Permit Areas, and any development permit issued will be in accordance with the guidelines of all such Areas.

### **Development Permit Area #1: Watercourse Development Permit (WDP) Area**

#### Category

The WDP area is designated under Section 919.1(1) (a) of the *Local Government Act* for the protection of the natural environment, its ecosystems and biological diversity.

#### Justification


The primary objective of this Development Permit Area designation is to regulate development activities in watercourses, lakes and wetlands and their adjacent riparian areas so as to protect aquatic habitat; and to conserve, enhance and, where necessary, restore watercourses and their riparian areas.

#### Area

The WDP area is comprised of:

1. Riparian assessment areas (Figure 1) for fish and wildlife habitat and drinking water, including:
  - a. All areas within 15 metres of the high water mark of a watercourse, including the natural boundary of a lake;
  - b. within 15 metres of the top of the ravine bank in the case of a ravine less than 60 metres wide;

- c. within 5 metres of the top of the ravine bank in the case of a wider ravine that links aquatic to terrestrial ecosystems and includes both existing and potential riparian vegetation and existing and potential upland vegetation that exerts an influence on the watercourse; and
- d. all areas within 15 metres of the high water mark of a wetland.



**FIGURE 1: RIPARIAN ASSESSMENT AREA:** means the area within 15 m of the high water mark of a watercourse; within 15 m of the top of the ravine bank in the case of a ravine less than 60 m wide; and within 5 m of the top of the ravine bank in the case of a wider ravine that link aquatic to terrestrial ecosystems and includes both existing and potential riparian vegetation and existing and potential upland vegetation that exerts an influence on the watercourse.

Source: British Columbia Ministry of Environment, *Riparian Areas Regulation Implementation Guidebook*, March 2005

Where the following definitions apply:

**High water mark** means the visible high water mark of a watercourse where the presence and action of the water are so common and usual, and so long continued in all ordinary years, as to mark on the soil of the bed of the watercourse a character distinct from that of its banks, in vegetation, as well as in the nature of the soil itself, and includes the active floodplain.

**Lake** means any area of year round open water covering a minimum of 1.0 hectares (2.47 acres) of area and possessing a maximum depth of at least 2.0 metres. Smaller and shallower areas of open water may be considered to meet the criteria of a wetland.

**Top of ravine bank** means the first significant break in a ravine slope where the break occurs such that the grade beyond the break is greater than 3:1 for a minimum distance of 15 m measured perpendicularly from the break, and the break does not include a bench within the ravine that could be developed.

**Watercourse** means any natural or man made depression with well-defined banks and a bed 0.6 metres (2.0 feet) or more below the surrounding land serving to give direction to a current of water at least six months of the year and/or having a drainage area of two square kilometres (0.8 square miles) or more upstream of the point of consideration.

**Wetland** means any areas that are inundated or saturated by surface or groundwater at a frequency and duration sufficient to support, and that under normal circumstances do support, a prevalence of vegetation typically adapted for life in saturated soil conditions. Wetlands generally include swamps, marshes, bogs and similar areas.

### **Guidelines**

A development permit is required, except where specified under the exemptions section, for development or land alteration on land identified as a riparian assessment area within the WDP Area. Where not exempt, development requiring a development permit includes any of the following associated with or resulting from residential, commercial or industrial activities or ancillary activities to the extent that they are subject to local government powers under local government legislation:

- a. removal, alteration, disruption or destruction of vegetation;
- b. disturbance of soils;
- c. construction or erection of buildings and structures;
- d. creation of non-structural impervious or semi-impervious surfaces;
- e. flood protection works;
- f. construction of roads, trails, docks, wharves and bridges;
- g. provision and maintenance of sewer and water services;
- h. development of drainage systems;
- i. development of utility corridors; and
- j. subdivision as defined in section 872 of the *Local Government Act*;

### **Development shall be in accordance with the following guidelines:**

2. All development proposals subject to this permit will be assessed by a Qualified Environmental Practitioner (QEP) or Registered Professional Biologist (RP Bio) in accordance with the Riparian Areas Regulation established by the Provincial and/or Federal governments as used elsewhere in the Province;

3. An WDP shall not be issued prior to the RDCK ensuring that a QEP or RP Bio has submitted a report certifying that they are qualified to carry out the assessment, that the assessment methods have been followed, and provides in their professional opinion that a lesser setback will not negatively affect the functioning of a watercourse or riparian area and that the criteria listed in the Riparian Areas Regulation has been fulfilled, and;
4. The Riparian Areas Regulation implemented through the WDP does not supersede other Federal, Provincial and or local government requirements, including that of other development permit areas, building permits, flood covenants, Federal or Provincial authorization. Land subject to more than one development permit area designation must ensure consistency with the guidelines of each development permit area, to provide comprehensive stewardship of both fish and wildlife habitat.

### **Exemptions**

The WDP area does not apply to the following:

5. existing construction, alteration, addition, repair, demolition and maintenance of farm buildings and agricultural activities including clearing of land for agricultural purposes;
6. existing institutional development containing no residential, commercial or industrial aspect;
7. construction, renovation, or repair of a permanent structure if the structure remains on its existing foundation. Only if the existing foundation is moved or extended in to a riparian assessment area would a WDP be required, and;
8. an area where the applicant can demonstrate that the conditions of the ESDP Area have already been satisfied or a development permit for the same area has already been issued in the past and the conditions in the development permit have all been met, or the conditions addressed in the previous development permit will not be affected.